


SUMMARY OF QUANTITIES				FUNDING: 80% FED : 20% STATE			
CONSTRUCTION CODE TYPE:			TOTAL	0004	0011	0011	0040
CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY	SN 008-0029 (EX) SN 008-0049 (PR)	SN 008-0030 (EX) SN 008-0050 (PR)	SN 008-1106 (PR)
51201600	FURNISHING STEEL PILES HP 12X53	FOOT	1145		425	720	
51201800	FURNISHING STEEL PILES HP 14X73	FOOT	600		600		
51202305	DRIVING PILES	FOOT	2140		1025	1115	
51203400	TEST PILE STEEL HP10X42	EACH	2			2	
51203600	TEST PILE STEEL HP 12X53	EACH	4		2	2	
51203800	TEST PILE STEEL HP 14X73	EACH	2		2		
51204650	PILE SHOES	EACH	60		28	32	
51500100	NAME PLATES	EACH	3		1	1	1
52100510	ANCHOR BOLTS, 3/4"	EACH	48		24	24	
52100520	ANCHOR BOLTS, 1"	EACH	48		24	24	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	118		58	60	
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	227	227			
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	164	164			
54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	216	216			

SPECIALTY ITEMS

FILE NAME *	USER NAME * USER*	DESIGNED - RAC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	 Zroka Engineering, P.C. 4216 North Hamitage Chicago, IL 60613	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILE# *	PLOT SCALE * SCALE*	DRAWN - LCR	REVISED -				17	4BR-5 & 4BR-6	CARROLL	150	9
	PLOT DATE * DATE*	CHECKED - OAZ	REVISED -				CONTRACT NO. 64083		ILLINOIS FED. AID PROJECT		
		DATE - 06-28-13	REVISED -	SCALE:	SHEET 5 OF 9 SHEETS	STA. TO STA.					

Rev.