


SUMMARY OF QUANTITIES

FUNDING: 80% FED : 20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE:			
				0004 ROADWAY	0011 SN 008-0029 (EX) SN 008-0049 (PR)	0011 SN 008-0030 (EX) SN 008-0050 (PR)	0040 SN 008-1106 (PR)
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1162	1162			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	950.0	950.0			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	825	825.0			
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4	4			
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4	4			
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	12120	12120			
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	40	40			
78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8			
78200520	BARRIER WALL MARKERS, TYPE B	EACH	8	8			
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8			
78300100	PAVEMENT MARKING REMOVAL	SO FT	2398	2398			
• A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10	10			
• A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10	10			
• B2001114	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10	10			

• SPECIALTY ITEMS

FILE NAME : #FILE#	USER NAME : #USER#	DESIGNED - RAC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	 Zroka Engineering, P.C. 4216 North Hermitage Chicago, IL 60611	SUMMARY OF QUANTITIES	F.A.P. RTE. 17	SECTION 4BR-5 & 4BR-6	COUNTY CARROLL	TOTAL SHEETS 150	SHEET NO. 12		
	PLOT SCALE : #SCALE#	DRAWN - LCR	REVISED -				SCALE:	SHEET 8 OF 9 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT			
	PLOT DATE : #DATE#	CHECKED - DAZ	REVISED -										
		DATE - 06-28-13	REVISED -										