



THE CONTRACTOR SHALL RESTORE A DISTURBED AREAS BY GRADING AND SEEDING. THIS WORK SHALL BE INCLUDED IN THE BID PRICE FOR THE PROPOSED CONDUIT.

SCHEDULE OF QUANTITIES (SHEET 12)		
UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	315.0
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	593.0
DRILL EXISTING HANDHOLE	EACH	1.0

FILE NAME = 68B58 Final Plans.dgn	USER NAME = keathbr	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 164.7568' / in.	CHECKED -	REVISED -
	PLOT DATE = 7/12/2013	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**FIBER OPTIC CABLE AND CONDUIT INSTALLATION  
I-74 WB RAMP AT STERLING AVE.**

SCALE: SHEET NO. 8 OF 62 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 ITS 2014	VARIOUS	22	11
CONTRACT NO. 68B58				
ILLINOIS FED. AID PROJECT				