



SCHEDULE OF QUANTITIES (SHEET 16)		
SERVICE INSTALLATION, TYPE B	EACH	1
UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	65.0
CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVS	FOOT	131.0
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	294.0
POLE MOUNTED EQUIPMENT CABINET, TYPE B	EACH	1.0
CAT 5 ETHERNET CABLE	FOOT	296.0

EC C XLP USE 1C 10  
98.0 FT. (X 3)

UNDRGRD C PVC 1  
65.0 FT.

FILE NAME = 68B58 Final Plans.dgn	USER NAME = keathbr	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 164.7568' / in.	CHECKED -	REVISED -
	PLOT DATE = 7/12/2013	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

CCTV CAMERA INSTALLATION  
UNDER PEKIN BRIDGE (WEST END)

SCALE: SHEET NO. 13 OF 62 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 ITS 2014	VARIOUS	22	16
CONTRACT NO. 68B58				
ILLINOIS FED. AID PROJECT				