

SUMMARY OF QUANTITIES

CODED NO	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				BRIDGE 025-0002 0014	BRIDGE 025-0019 0014	BRIDGE 025-0062 0014	
	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1013.6	434	579.6		
	POROUS GRANULAR EMBANKMENT	CU YD	1013.6	434	579.6		
	PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	442	442			
	PAVEMENT FABRIC	SQ YD	442	442			
	PROTECTIVE COAT	SQ YD	442	442			
	PAVED SHOULDER REMOVAL	SQ YD	442	442			
	AGGREGATE WEDGE SHOULDER, TYPE B	TON	137			137	
	CONCRETE REMOVAL	CU YD	90.7	48.1	42.6		
	SLOPE WALL REMOVAL	SQ YD	1353.6	571	768	14.6	
	PROTECTIVE SHIELD	SQ YD	450	286	164		
	STRUCTURE EXCAVATION	CU YD	37.7	19	9.1	9.6	
	CONCRETE STRUCTURES	CU YD	113.8	48.5	39.8	25.5	
	RUBBED FINISH	SQ FT	377	172	205		
	CONCRETE SUPERSTRUCTURE	CU YD	127.6	48.2	79.4		
	BRIDGE DECK GROOVING	SQ YD	764	693	71		
	PROTECTIVE COAT	SQ YD	325.3	133.2	192.1		
	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	24530	9390	9720	5420	
	REINFORCEMENT BARS, EPOXY COATED	POUND	34390	12480	18210	3700	
	BAR SPLICERS	EACH	117	68	35	14	
	STEEL RAILING, TYPE 2399	FOOT	450			450	
	SLOPE WALL 4 INCH	SQ YD	1524.4	650.6	863.8	10	
	PREFORMED JOINT STRIP SEAL	FOOT	409.5	221	188.5		
	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	46	18	8	20	
	ANCHOR BOLTS, 5/8"	EACH	16		16		
	ANCHOR BOLTS, 1"	EACH	152	72		80	
	ANCHOR BOLTS, 1 1/4"	EACH	32		32		
	CONCRETE SEALER	SQ FT	4675	2332	1304	1039	
	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	200			200	
	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4			4	
	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4			4	
	GUARDRAIL REMOVAL	FOOT	409			409	
	MOBILIZATION	L SUM	0.1			0.1	
	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1			1	
	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1			1	
	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1			1	
	TRAFFIC CONTROL SURVEILLANCE	CAL DA	7	1	1	5	
	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1			1	
	TEMPORARY CONCRETE BARRIER	FOOT	228	228			
	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	228	228			
	GUARDRAIL MARKERS, TYPE A	EACH	4			4	
	GUARDRAIL MARKERS, TYPE B	EACH	6			6	
	TERMINAL MARKER - DIRECT APPLIED	EACH	4			4	
	SEISMIC RESTRAINER	EACH	38	12	16	10	
	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	0.02	0.01	0.01		

CODED NO	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				BRIDGE 025-0002 0014	BRIDGE 025-0019 0014	BRIDGE 025-0062 0014	
	TRAFFIC CONTROL AND PROTECTION (DETOUR)	L SUM	0.5		0.5		
	JACK AND REMOVE EXISTING BEARINGS	EACH	64	36	8	20	
	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1			1	
	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1			1	
	BRIDGE DECK FLY ASH OR GGBF SLAG CONCRETE OVERLAY, 2 1/2"	SQ YD	658	658			
	BRIDGE DECK SCARIFICATION 2 1/2"	SQ YD	658	658			
	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	383	178	205		
	CONCRETE REMOVAL (SPECIAL)	SQ YD	13.9	10	3.9		
	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	27	27			
	DRAINAGE SYSTEM	L SUM	0.25		0.25		

REV 09/04/13