

SUMMARY OF QUANTITIES

90% FED
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				URBAN		(25-4)R			(25-4HVB-1)BY		(25-4)BR	
				ROADWAY 0003	ROADWAY 0005	SIGNALS LIGHTING 0021	SN 025-0111 (WB) 0010	SN 025-8648 0040	SN 025-0002 0014	SN 025-0019 0014	SN 025-0062 0014	
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	1802	1802								
44000600	SIDEWALK REMOVAL	SQ FT	1152	1152								
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	17147	17147								
44004000	PAVED DITCH REMOVAL	FOOT	1695	1695								
44004250	PAVED SHOULDER REMOVAL	SQ YD	59160	58718					442			
44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SQ YD	87	87								
44201043	CLASS B PATCHES, TYPE II, 16 INCH	SQ YD	67	67								
44201047	CLASS B PATCHES, TYPE III, 16 INCH	SQ YD	32	32								
44201299	DOWEL BARS 1 1/2"	EACH	260	260								
44213100	PAVEMENT FABRIC	SQ YD	119	119								
44213200	SAW CUTS	FOOT	721	721								
44213204	TIE BARS 3/4"	EACH	25	25								
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5393	5393								
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	294		157							137