

SUMMARY OF QUANTITIES

90% FED
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				URBAN			(25-4)R		(25-4HVB-1)BY		(25-4)BR	
				ROADWAY 0003	ROADWAY 0005	SIGNALS LIGHTING 0021	SN 025-0111 (WB) 0010	SN 025-0112 (EB) 0040	SN 025-0002 0014	SN 025-0019 0014	SN 025-0062 0014	
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1804	1804								
63500105	DELINEATORS	EACH	477	477								
63700175	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	753	753								
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	6217	6217								
63700900	CONCRETE BARRIER BASE	FOOT	7729	7729								
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	93859	81158	12701							
66500105	WOVEN WIRE FENCE, 4'	FOOT	3486	3486								
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	74	74								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	30	30								
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	30	30								
67100100	MOBILIZATION	L SUM	1	0.9								0.1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1									1
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1									1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2		2							

FILE NAME *	USER NAME * #USER*	DESIGNED - ESW	REVISED -
20-projects\403-8807-57-20\p18-14-1\summary_combined.dwg		DRAWN - ESW	REVISED -
		CHECKED - BRM	REVISED -
		DATE - 08-28-09	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

COMBINED SUMMARY OF QUANTITIES, NORTH TRI LEVEL

SCALE: SHEET NO. 13 OF 27 SHEETS STA. TO STA.

F.A.I. R.T.E. 57/10	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		EFFINGHAM	1760	15
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 74295	

* (25-4)R & (25-4HVB-1)BY & (25-4)BR