SUMMARY OF QUANTITIES

90% FED
10% STATE

URBAN

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE (25-4)R ROADWAY 0003	(25-4)R ROADWAY 0005	(25-4)R SIGNALS LIGHTING 0021	(25-4HVB-1)BY SN 025-0111 (WB) SN 025-0112 (EB) 0010	(25-4HVB-1)BY SN 025-8648 0040	(25-4)BR SN 025-0002 0014	(25-4)BR SN 025-0019 0014	(25-4)BR SN 025-0062 0014
*	81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	1895			1895					
*	81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	14709			14709					
*	81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	13674			13674					
*	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	178			178					
*	82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	4			4					
*	82109105	SIGN LIGHTING (HIGH PRESSURE SODIUM)	EACH	30			30					
*	82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP	EACH	1			1					
*	82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP	EACH	2			2					
*	82500380	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 200AMP	EACH	1			1					
*	83003350	LIGHT POLE, ALUMINUM, 45 FT. M.H., 8 FT. DAVIT ARM - TWIN	EACH	31			31					
*	83004600	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM	EACH	106			106					
*	83053150	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM, TWIN	EACH	5			5					
*	83600357	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	107			107					
*	83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	380			380					

* SPECIALTY ITEM

*(25-4)R & (25-4HVB-1)BY & (25-4)BR

FILE NAME =	USER NAME = $USER$	DESIGNED - ESW	REVISED -
		DRAWN - ESW	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - BRM	REVISED -
	PLOT DATE = $DATE$	DATE - 08-28-09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

COMBINED SUMMARY OF QUANTITIES, NORTH TRI LEVEL

SCALE: | SHEET NO. 19 OF 27 SHEETS | STA. | TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/70	*	EFFINGHAM	1760	21

CONTRACT NO. 74295

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT