

SUMMARY OF QUANTITIES

90% FED
10% STATE

CONSTRUCTION CODE

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				(25-4)R		SIGNALS LIGHTING 0021	(25-4)HVB-1)BY		(25-4)BR			
				ROADWAY 0003	ROADWAY 0005		SN 025-0111 (WB) 0010	SN 025-8648 0040	SN 025-0002 0014	SN 025-0019 0014	SN 025-0062 0014	
* 84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	19			19						
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	10			10						
* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	4			4						
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2			2						
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	4			4						
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1			1						
* 85800100	FLASHER CONTROLLER	EACH	1			1						
* 86200300	UNINTERRUPTABLE POWER SUPPLY, EXTENDED	EACH	1			1						
* 86300300	CONTROLLER CABINET TYPE III	EACH	1	1								
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	790			790						
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2017			2017						
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1467			1467						
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3905			3905						
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	35			35						

*SPECIALTY ITEM

* (25-4)R & (25-4)HVB-1)BY & (25-4)BR

FILE NAME :	USER NAME : *USER*	DESIGNED - ESW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	COMBINED SUMMARY OF QUANTITIES, NORTH TRI LEVEL			F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S:\projects\101\10171\10171.dwg		DRAWN - ESW	REVISED -					57/70		EFFINGHAM	1760	22
		CHECKED - BRM	REVISED -					CONTRACT NO. 74295			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	
		DATE - 08-28-09	REVISED -					SCALE:	SHEET NO. 20 OF 27 SHEETS	STA.	TO STA.	