

SUMMARY OF QUANTITIES

90% FED  
10% STATE

CONSTRUCTION CODE

URBAN

| CODE NO.   | ITEM   | UNIT  | TOTAL QUANTITY | CONSTRUCTION CODE |              |                  |                       |                  |                  |                  |                  |  |
|------------|--|-------|----------------|-------------------|--------------|------------------|-----------------------|------------------|------------------|------------------|------------------|--|
|            |  |       |                | (25-4)R           |              | SIGNALS LIGHTING | (25-4HVB-1)BY         |                  | (25-4)BR         |                  |                  |  |
|            |  |       |                | ROADWAY 0003      | ROADWAY 0005 |                  | SN 025-0111 (WB) 0010 | SN 025-8648 0040 | SN 025-0002 0014 | SN 025-0019 0014 | SN 025-0062 0014 |  |
| * 88040230 | SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED            | EACH  | 1              |                   |              | 1                |                       |                  |                  |                  |                  |  |
| * 88040290 | SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED            | EACH  | 1              |                   |              | 1                |                       |                  |                  |                  |                  |  |
| * 88200410 | TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC                             | EACH  | 12             |                   |              | 12               |                       |                  |                  |                  |                  |  |
| * 88500100 | INDUCTIVE LOOP DETECTOR  | EACH  | 14             |                   |              | 14               |                       |                  |                  |                  |                  |  |
| * 88600100 | DETECTOR LOOP, TYPE I  | FOOT  | 2182           | 1045              |              | 1137             |                       |                  |                  |                  |                  |  |
| * 88700200 | LIGHT DETECTOR   | EACH  | 3              |                   |              | 3                |                       |                  |                  |                  |                  |  |
| * 88700300 | LIGHT DETECTOR AMPLIFIER   | EACH  | 1              |                   |              | 1                |                       |                  |                  |                  |                  |  |
| * 89502400 | REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE                          | EACH  | 1              |                   |              | 1                |                       |                  |                  |                  |                  |  |
| * D2002972 | EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 6' HEIGHT, BALLED AND BURLAPPED | EACH  | 900            | 900               |              |                  |                       |                  |                  |                  |                  |  |
| X0301242   | PIEZO AXLE SENSOR, CLASS II  | FOOT  | 66             | 66                |              |                  |                       |                  |                  |                  |                  |  |
| X0321778   | SEISMIC RESTRAINER   | EACH  | 38             |                   |              |                  |                       | 12               | 16               | 10               |                  |  |
| X0322278   | RODENT SHIELDS   | EACH  | 129            | 129               |              |                  |                       |                  |                  |                  |                  |  |
| * X0322792 | BEDDING MATERIAL, SPECIAL  | CU YD | 213.3          | 213.3             |              |                  |                       |                  |                  |                  |                  |  |
| X0323149   | TEMPORARY MECHANICALLY STABILIZED EARTH RETAINING WALL                         | SQ FT | 5825           | 5825              |              |                  |                       |                  |                  |                  |                  |  |

CITY

\*SPECIALTY ITEM

|                       |                    |                 |           |   |   |                    |                           |           |              |                     |                             |
|-----------------------|--------------------|-----------------|-----------|---|---|--------------------|---------------------------|-----------|--------------|---------------------|-----------------------------|
| FILE NAME :           | USER NAME : #USERS | DESIGNED - ESW  | REVISED - | STATE OF ILLINOIS<br>DEPARTMENT OF TRANSPORTATION | COMBINED SUMMARY OF QUANTITIES, NORTH TRI LEVEL | F.A.I. RTE.        | SECTION                   | COUNTY    | TOTAL SHEETS | SHEET NO.           |                             |
| 5/14/2009 10:00:00 AM |                    | DRAWN - ESW     | REVISED - |   |   | 57/70              | *                         | EFFINGHAM | 1760         | 24                  |                             |
| PLOT SCALE : #SCALE#  |                    | CHECKED - BRM   | REVISED - |   |   | CONTRACT NO. 74295 |                           |           |              |                     |                             |
| PLOT DATE : #DATE#    |                    | DATE - 08-28-09 | REVISED - |   |   | SCALE:             | SHEET NO. 22 OF 27 SHEETS | STA.      | TO STA.      | FED. ROAD DIST. NO. | [ILLINOIS] FED. AID PROJECT |

\* (25-4)R & (25-4HVB-1)BY & (25-4)BR