

SUMMARY OF QUANTITIES - CONT

CODE NUMBER	ITEM DESCRIPTION	UNIT	CONSTRUCTION TYPE CODE: 0040 FUNDING: 80% FED 20% STATE
44000100	PAVEMENT REMOVAL	SQ YD	391
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	713
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,610
54003000	CONCRETE BOX CULVERTS	CU YD	30.8
54010907	PRECAST CONCRETE BOX CULVERTS 9' X 7'	FOOT	96
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	337.5
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	45.5
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	785
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1

*SPECIALTY ITEM

FILE NAME =	USER NAME = walorra	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pcc\work\pccdot\walorra\d0326424\703	2-Design.dgn	DRAWN - _____	REVISED - _____			332	2B-2	WHITE	23	4	
Default	PLOT SCALE = 1/8"=1'-0"	CHECKED - _____	REVISED - _____			SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____		ILLINOIS FED. AID PROJECT CONTRACT NO. 78312			
	PLOT DATE = 5/29/2013	DATE - _____	REVISED - _____								