



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 5, 2019

SUBJECT: FAI Route 90/94 (I-90/94)
Section 2018-0144-I
Cook County
Contract No. 62H74
Item No. 15, September 20, 2019 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised sheet 3 of the Plans.
3. Revised the Table of Contents of the Special Provisions.
4. Added page 68 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
STATUS OF UTILITIES (D-1)	2
PUBLIC CONVENIENCE AND SAFETY (DIST 1)	3
BITUMINOUS PREMIX FOR MAINTENANCE USE (MATERIAL SPECIFICATION M 120-16).....	4
RAISED REFLECTIVE PAVEMENT MARKER	6
TRAFFIC CONTROL PLAN	7
SPEED DISPLAY TRAILER (D1)	8
KEEPING THE EXPRESSWAY OPEN TO TRAFFIC	10
FAILURE TO OPEN TRAFFIC LANES TO TRAFFIC	14
TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS).....	14
TRAFFIC CONTROL FOR WORK ZONE AREAS	18
PREFORMED PLASTIC PAVEMENT MARKING TYPE D – D-1	19
RAISED REFLECTIVE PAVEMENT MARKER	22
COMPENSABLE DELAY COSTS (BDE).....	23
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	27
CONTRAST PREFORMED PLASTIC PAVEMENT MARKING (BDE).....	29
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	30
DISPOSAL FEES (BDE)	41
EQUIPMENT PARKING AND STORAGE (BDE)	42
GROOVING FOR RECESSED PAVEMENT MARKINGS (BDE).....	43
LIGHTS ON BARRICADES (BDE)	46
PAVEMENT MARKING REMOVAL (BDE)	47
PAYMENTS TO SUBCONTRACTORS (BDE)	48
PREFORMED PLASTIC PAVEMENT MARKING TYPE D - INLAID (BDE)	48
PROGRESS PAYMENTS (BDE)	51
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	52
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	64
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	64
TRAFFIC CONTROL DEVICES - CONES (BDE).....	65
TRAFFIC SPOTTERS (BDE).....	66
WEEKLY DBE TRUCKING REPORTS (BDE).....	67
WORKING DAYS (BDE)	67
RAISED REFLECTIVE PAVEMENT MARKER	68

Revised 9-5-2019

RAISED REFLECTIVE PAVEMENT MARKER

Description. This work shall consist of removing damaged raised reflective pavement marker castings, repairing the existing pavement after the damaged casting has been removed, the installation of a new raised reflective pavement marker complete with reflector or replacing individual reflectors as directed by the Engineer. This work shall be completed according to Section 781 and 783 of the Standard Specifications.

The removal and replacement of the damaged casting shall be completed at the same time as the reflectors are being replaced on the route.

Raised Reflective Pavement Marker Removal. This work shall be according to Section 783 of the Standard Specifications.

Pavement Repair.

The hole resulting from the removal of the raised reflective pavement marker casting in Bituminous Concrete surfaces shall be cleaned out with compressed air, repaired with a Bituminous Premix For Maintenance Use (Material Specification M 120-16) and compacted to the satisfaction of the Engineer. For those locations where the casting is missing and there is an existing hole, the existing hole shall be cleaned with compressed air and repaired with a Bituminous Premix For Maintenance Use (Material Specification M 120-16) and compacted to the satisfaction to the Engineer. The cost of repairing the existing hole shall be considered as included to the cost of the contract.

The hole resulting from the removal of the raised reflective pavement marker casting in Portland Cement Concrete pavement shall be cleaned out with compressed air, repaired with a rapid setting epoxy according to Article 781.03 and to the satisfaction of the Engineer. For those locations where the casting is missing and there is an existing hole, the existing hole shall be cleaned with compressed air and repaired with a rapid setting epoxy according to Article 781.03 and to the satisfaction of the Engineer. The cost of repairing the existing hole shall be considered as included to the cost of the contract.

Raised Reflective Pavement Marker Casting with Reflectors. Installation of the replacement raised reflector pavement marker casting with reflector shall meet the requirements of Section 781 of the Standard Specifications.

- (c) To ensure proper installation of the replacement raised pavement marker, the marker shall be located fore or aft of the damaged casting location and on the proper alignment or as directed by the Engineer.

Replacing Reflectors. Replacement of reflectors shall be according to Section 781 of the Standard Specifications and the following.

Method of Measurement. This work will be measured for payment as follows:

- (c) Measured Quantities. This work will be measured for payment per each marker removed and replaced and for each reflector replaced.

Basis of Payment. This work will be paid for at the contract unit price per each for RAISED REFLECTIVE PAVEMENT MARKER REMOVAL, at the contract unit price per each for RAISED REFLECTIVE PAVEMENT MARKER or at the contract unit price per each for REPLACEMENT REFLECTOR.