CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: FAP 103 (NHPP) ROADWAY 0021 URBAN	ROADWAY 0005 URBAN	ROADWAY 0005 RURAL
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	5		5	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	9	9		
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	93,935	2,489	27,511	63,935
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N70	TON	5,818	128	1,712	3,978
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	636	407	36	193
40600990	TEMPORARY RAMP	SQ YD	2,709	407	1,451	851
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	12,039	310	3,424	8,305
40700100	BITUMINOUS MATERIALS (TACK COAT)	POUND	20		20	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	2	2		
42000400	PORTLAND CEMENT CONCRETE PAVEMENT9"	SQ YD	12	12		
42400800	DETECTABLE WARNINGS	SQ FT	624	624		
44000100	PAVEMENT REMOVAL	SQ YD	49	49		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL,2"	SQ YD	139,414	3,542	46,019	89,853
44000159	HOT-MIX ASPHALT SURFACE REMOVAL,2 1/2"	SQ YD	43,400		0	43,400
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	23	23		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: FAP 103 (NHPP) ROADWAY 0021 URBAN	ROADWAY 0005 URBAN	ROADWAY 0005 RURAL
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,022	942	80	
44000600	SIDEWALK REMOVAL	SQ FT	7,127	7,127		
44004250	PAVED SHOULDER REMOVAL	SQ YD	9		9	
44200116	PAVEMENT PATCHING, TYPE I,10 INCH	SQ YD	5			5
44200120	PAVEMENT PATCHING, TYPE II,10 INCH	SQ YD	9			9
44200124	PAVEMENT PATCHING, TYPE III, 10 INCH	SQ YD	115			115
44200140	PAVEMENT PATCHING, TYPE I,12 INCH	SQ YD	5		5	
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	28		28	
44200150	PAVEMENT PATCHING, TYPE IV,12 INCH	SQ YD	46		46	
44200168	PAVEMENT PATCHING, TYPE II,14 INCH	SQ YD	46			46
44200174	PAVEMENT PATCHING, TYPE IV,14 INCH	SQ YD	92			92
44200201	PAVEMENT PATCHING, TYPE I,17 INCH	SQ YD	5		5	
44200202	PAVEMENT PATCHING, TYPE II,17 INCH	SQ YD	25			25
44200204	PAVEMENT PATCHING, TYPE III, 17 INCH	SQ YD	1,328		276	1,052
44200206	PAVEMENT PATCHING, TYPE IV,17 INCH	SQ YD	2,425		74	2,351

REV. - MS

MODEL: Default
FILE NAME: 76J16_03-Sht-Quan-Summary-01.dgn

USER NAME = gowens	DESIGNED - GDO	REVISED -
	DRAWN - GDO	REVISED -
PLOT SCALE = 2.0000 ' / in.	CHECKED - STS	REVISED -
PLOT DATE = 3/22/2019	DATE - 3/22/2019	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: 2.0000 ' / in. | SHEET 1 OF 3 SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	(27,25,38,561)RS	ST. CLAIR	87	3
		CONTRACT NO. 76J16		
		ILLINOIS FED. AID PROJECT		