

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				FAP 103 (NHPP)	ROADWAY	ROADWAY
				0021 URBAN	0005 URBAN	0005 RURAL
* 78004358	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - INLAID - LINE 8"	FOOT	83		83	0
* 78004362	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - INLAID - LINE 12"	FOOT	1,391		1,087	304
* 78004374	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - INLAID - LINE 24"	FOOT	588		588	0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	902		451	451
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	941		488	453
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	130	130		
* 81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	122	122		
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 142C	FOOT	1,064	1,064		
* 87600200	PEDESTRIAN PUSH-BUTTON POST, TYPE II	EACH	15	15		
* 87900200	DRILL EXISTING HANDHOLE	EACH	13	13		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,939	2,939		
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	15	15		
* 89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	6,520	6,520		
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4	4		
* X2700006	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 4"	FOOT	127,148		33,668	93,480

\* SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				FAP 103 (NHPP)	ROADWAY	ROADWAY
				0021 URBAN	0005 URBAN	0005 RURAL
X4230710	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH, SPECIAL	SQ YD	20	20		
X4240420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SQ FT	8,261	8,261		
X4240440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	83	83		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	146	146		
X6060068	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL) (ABUTTING EXISTING PAVEMENT)	FOOT	47	47		
X6660445	RIGHT OF WAY AND PROPERTY CORNERS	EACH	41	41		
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	46,191		14,647	31,544
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	127,148		33,668	93,480
* X8800101	PEDESTRIAN PUSH-BUTTON, SPECIAL	EACH	3	3		
Z0007430	TEMPORARY SIDEWALK	SQ FT	1,782	1,782		
Z0012455	CONCRETE STEP REMOVAL	EACH	1	1		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0033700	LONGITUDINAL JOINT SEALANT	FOOT	58,090		23,470	34,620
Z0034105	MATERIAL TRANSFER DEVICE	TON	17,857	438	5,135	12,283
Ø Z0076600	TRAINEES	HOUR	2,000	2,000		
Z0036200	PAINT CURB	FOOT	290		130	160
Ø Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	2,000	2,000		
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	24		2	22

Ø 0042

MODEL: Default  
FILE NAME: 76116 Data-Sht-Quant-Summary-01.dgn

REV. - MS

USER NAME = gowens	DESIGNED - GDO	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 2,0000' / in.	DRAWN - GDO	REVISED -					103	(27,25,38,56)RS	ST. CLAIR	87	5
PLOT DATE = 3/22/2019	CHECKED - STS	REVISED -		SCALE: 2,0000' / in.	SHEET 3 OF 3 SHEETS	STA. TO STA.	CONTRACT NO. 76116				
	DATE - 3/22/2019	REVISED -		ILLINOIS FED. AID PROJECT							