

PAVEMENT PATCHING 17 INCH SCHEDULE							
LOCATION	LANE	LENGTH (FT)	LANE WIDTH (FT)	PAVEMENT PATCHING TYPE I (SQ. YD.)	PAVEMENT PATCHING TYPE II (SQ. YD.)	PAVEMENT PATCHING TYPE III (SQ. YD.)	PAVEMENT PATCHING TYPE IV (SQ. YD.)
387+87	All	6.0	36.0			24.0	
388+40	Turn Lane	6.0	36.0			24.0	
420+08	All	8.0	24.0			21.3	
424+83	All	8.0	24.0			21.3	
425+36	All	6.0	24.0			16.0	
430+64	SB	6.0	24.0			16.0	
431+17	All	12.0	24.0				32.0
433+28	SB	6.0	24.0			16.0	
437+50	All	8.0	24.0			21.3	
438+56	All	6.0	24.0			16.0	
440+14	All	8.0	24.0			21.3	
441+20	All	12.0	24.0				32.0
442+78	All	8.0	24.0			21.3	
443+84	SB	6.0	6.0	4.0			
446+48	NB	8.0	24.0			21.3	
URBAN SUBTOTAL:				4.0		240.0	64.0
ANTICIPATED FAILURES (15%):				0.6		36.0	9.6
448+06	All	6.0	24.0			16.0	
449+12	All	10.0	24.0				26.7
451+76	All	10.0	24.0				26.7
453+34	All	6.0	24.0			16.0	
454+93	SB	6.0	24.0			16.0	
455+46	SB	30.0	24.0				80.0
455+98	NB	8.0	24.0			21.3	
457+04	All	6.0	24.0			16.0	
458+62	All	6.0	24.0			16.0	
460+74	All	6.0	24.0			16.0	
462+32	All	10.0	24.0				26.7
463+90	All	8.0	24.0			21.3	
472+88	All	8.0	24.0			21.3	
474+46	All	10.0	24.0				26.7
478+16	All	20.0	24.0				53.3
480+80	All	15.0	24.0				40.0
483+44	All	10.0	24.0				26.7
486+08	NB	20.0	24.0				53.3
488+72	All	8.0	24.0			21.3	
490+30	NB	30.0	24.0				80.0
490+83	NB	15.0	24.0				40.0
490+83	SB	15.0	24.0				40.0
491+89	NB	30.0	24.0				80.0
493+47	All	10.0	24.0				26.7
494+00	All	6.0	24.0			16.0	
495+58	All	6.0	24.0			16.0	
496+11	NB	12.0	24.0				32.0
546+80	SB	30.0	6.0			20.0	
548+38	All	6.0	24.0			16.0	
552+08	All	12.0	24.0				32.0
557+36	All	6.0	24.0			16.0	
558+94	All	8.0	24.0			21.3	
562+64	All	6.0	24.0			16.0	
564+22	SB	10.0	24.0				26.7
567+92	NB	12.0	24.0				32.0
569+50	All	10.0	24.0				26.7
570+03	All	6.0	24.0			16.0	
573+20	All	10.0	24.0				26.7
575+84	All	10.0	24.0				26.7
578+48	All	6.0	24.0			16.0	
580+06	All	6.0	24.0			16.0	
581+12	All	8.0	24.0			21.3	
583+76	All	10.0	24.0				26.7
589+04	All	30.0	24.0				80.0
594+32	All	6.0	24.0			16.0	
595+90	All	30.0	24.0				80.0
596+96	All	6.0	24.0			16.0	
598+54	All	6.0	24.0			16.0	
599+60	All	8.0	24.0			21.3	
602+24	All	20.0	24.0				53.3
604+88	All	15.0	24.0				40.0
610+16	SB	6.0	24.0			16.0	
611+74	NB	12.0	24.0				32.0
615+44	All	8.0	24.0			21.3	
620+72	All	10.0	24.0				26.7
626+00	All	20.0	24.0				53.3
631+28	All	12.0	24.0				32.0
652+40	All	8.0	24.0			21.3	
657+68	All	20.0	24.0				53.3
662+96	All	6.0	24.0			16.0	
664+54	All	6.0	24.0			16.0	
665+60	SB	12.0	6.0		8.0		
673+52	All	12.0	24.0				32.0
689+36	All	8.0	24.0			21.3	
694+64	All	8.0	24.0			21.3	
699+92	All	8.0	24.0			21.3	
701+50	NB	20.0	6.0			13.3	
705+20	All	10.0	24.0				26.7
706+78	All	8.0	24.0			21.3	
710+48	All	8.0	24.0			21.3	
715+76	All	12.0	24.0				32.0
718+40	All	20.0	24.0				53.3
RURAL SUBTOTAL:					21.3	914.7	2044.3
ANTICIPATED FAILURES (15%):					3.2	137.2	306.6
TOTAL:				5	25	1328	2425

SIDEROAD/ENTRANCE SCHEDULE									
CL OF ENTRANCE OR SIDEROAD	LOCATION	RAMP LENGTH	(SQ YD)	REMARKS	CL OF ENTRANCE OR SIDEROAD	LOCATION	RAMP LENGTH	(SQ YD)	REMARKS
339+28	LT	68	23		404+88	LT	32	11	
340+38	RT	67	22		405+26	RT	36	12	
341+03	LT	60	20		405+68	LT	42	14	
341+64	RT	55	18		406+47	RT	59	20	
342+75	LT	46	15	WUEST LN	406+53	LT	63	21	
344+50	RT	205	68	MAIN ST	406+60	RT	45	15	
347+05	RT	63	21		408+75	LT	282	94	IL 15/URBANNA DR
347+70	RI	39	13		411+37	RI	65	22	
348+55	LT	65	22	MEADOW RIDGE DR	411+41	LT	32	11	
351+53	LT	168	56		413+15	RT	58	19	
354+09	RT	41	14		414+35	LT	85	28	SOUTHGATE DR
355+75	LT	156	52	MARKETPLACE DR	415+95	LT & RT	147	49	HIL. MINE RD
358+38	LT	129	43		427+30	LT	43	14	
361+83	LT	35	12		427+95	RT	35	12	
364+51	LT	34	11		431+78	LT	50	17	
365+00	RT	27	9		434+28	RT	34	11	
365+03	LT	37	12		436+36	LT	62	21	
365+65	RT	27	9		436+72	RT	34	11	
367+88	RT	23	8		441+16	RT	23	8	
368+82	LT	27	9		441+71	RT	19	6	
371+48	RT	27	9		442+16	LT	43	14	
372+35	RT	36	12		445+10	LT & RT	320	107	COMMERCE DR
373+29	LT	25	8		URBAN SUBTOTAL: 1451				
373+32	RT	42	14		456+39	RT	254	85	
374+82	RT	49	16		468+15	LT & RT	128	43	PRESS RD
375+18	LT	25	8		472+93	RT	27	9	
375+76	RT	52	17		474+14	RT	27	9	
375+77	LT	25	8		480+06	LT	43	14	
382+07	RT	26	9		494+40	LT	56	19	
383+35	LT	55	18		499+93	LT	45	15	
385+34	LT	85	28		502+85	LT	114	38	RED RAY MINE RD
385+92	RT	55	18		545+02	LT	61	20	
386+14	LT	27	9		548+29	LT	80	27	
386+55	RT	55	18		548+58	RT	89	30	BLACKSMITH SHOP RD
386+81	LT	46	15		549+66	RT	54	18	
389+82	RT	47	16		550+14	LT	63	21	
392+45	LT	79	26		552+98	RT	25	8	
393+58	LT	39	13		559+71	RT	43	14	
393+85	RT	21	7		563+35	RT	30	10	
394+41	LT	36	12		569+10	LT	45	15	LEMONTON RD
395+18	RT	19	6		572+26	RT	70	23	
395+55	LT	45	15		589+72	RT	42	14	
396+09	LT	43	14		602+95	RT	96	32	ROBINSON SCHOOL RD
396+82	LT & RT	141	47		602+95	LT	88	29	5 FORKS EAST RD
397+73	RT	17	6		604+06	LT	36	12	
397+96	RT	20	7		616+72	RT	45	15	
399+25	RT	20	7		619+10	RT	33	11	
400+20	RT	20	7		648+56	LT	49	16	
402+05	LT	53	18	SOUTH ST	655+89	RT	69	23	
402+89	LT	24	8		676+04	RT	117	39	
402+94	RT	34	11		692+70	LT	42	14	
403+22	LT	26	9		698+25	LT	60	20	WERNER RD
403+54	LT	16	5		711+85	RT	71	24	CALAMUS LAKE SCHOOL RD
403+85	RT	26	9		738+80	LT & RT	551	184	IL 156
404+51	LT	22	7		RURAL SUBTOTAL: 851				
					TOTAL: 2302				

PAVEMENT PATCHING 10 INCH SCHEDULE						
LOCATION	LANE	LENGTH (FT)	LANE WIDTH (FT)	PAVEMENT PATCHING TYPE I (SQ. YD.)	PAVEMENT PATCHING TYPE II (SQ. YD.)	PAVEMENT PATCHING TYPE III (SQ. YD.)
742+16	NB	30.0	6.0			20.0
747+44	SB	12.0	6.0		8.0	
749+02	SB	6.0	6.0	4.0		
752+72	All	6.0	24.0			16.0
754+30	All	6.0	24.0			16.0
758+00	All	6.0	24.0			16.0
763+28	SB	6.0	24.0			16.0
773+84	All	6.0	24.0			16.0
RURAL SUBTOTAL:				4.0	8.0	100.0
ANTICIPATED FAILURES (15%):				0.6	1.2	15.0
TOTAL:				5	9	115

PAVEMENT PATCHING 12 INCH SCHEDULE						
LOCATION	LANE	LENGTH (FT)	LANE WIDTH (FT)	PAVEMENT PATCHING TYPE I (SQ. YD.)	PAVEMENT PATCHING TYPE III (SQ. YD.)	PAVEMENT PATCHING TYPE IV (SQ. YD.)
398+96	NB	6.0	6.0	4.0		
402+13	Lincoln St. Intersection	60.0	6.0			40.0
405+82	All	6.0	36.0		24.0	
URBAN SUBTOTAL:				4.0	24.0	40.0
ANTICIPATED FAILURES (15%):				0.6	3.6	6.0
TOTAL:				5	28	46

PAVEMENT PATCHING 14 INCH SCHEDULE						
LOCATION	LANE	LENGTH (FT)	LANE WIDTH (FT)	PAVEMENT PATCHING TYPE II (SQ. YD.)	PAVEMENT PATCHING TYPE IV (SQ. YD.)	
525+68	NB	20.0	6.0	13.3		
527+26	NB	20.0	6.0	13.3		
527+79	NB	20.0	6.0	13.3		
528+32	NB	30.0	24.0			80.0
RURAL SUBTOTAL:				40.0	80.0	
ANTICIPATED FAILURES (15%):				6.0	12.0	
TOTAL:				46	92	

FAP route 103 (IL-13/15) Contract D876J16				
Schedule of Quantities: Right-of-Way Markers and Right-of-Way and Property Corners				
Route	Station	Offset	Direction	Right-of-Way and Property Corners - Pay Item: X6660445
IL 13/15	363+70.53	32.39'	Rt	1
IL 13/15	364+04.52	27.07'	Rt	1
IL 13/15	366+46.33	25.68'	Lt	1
IL 13/15	366+55.45	27.06'	Rt	1
IL 13/15	366+75.33	47.18'	Rt	1
IL 13/15	366+76.41	50.39'	Lt	1
IL 13/15	370+01.50	25.75'	Lt	1
IL 13/15	370+05.50	27.00'	Rt	1