

MODEL: D:\rout\1\p\lancrcomdet\illinoisgwp\DDT\Documents\DDT OF Fees\District 4\Projects\04-68758\0400\04-68758-CAD\04-68758-CAD\04-68758-ht-500.dgn  
 FILE NAME: P:\p\lancrcomdet\illinoisgwp\DDT\Documents\DDT OF Fees\District 4\Projects\04-68758\0400\04-68758-CAD\04-68758-CAD\04-68758-ht-500.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY	BRIDGE	
				0004	0010	
				RURAL	S. N. 048-0095	
				KNOX	KNOX	
20100110	TREE REMOVAL ( 6 TO 15 UNITS DIAMETER)	UNIT	26	26		
20100500	TREE REMOVAL, ACRES	ACRE	0.4	0.4		
20200100	EARTH EXCAVATION	CU YD	5906	5906		
20200500	EARTH EXCAVATION ( WIDENING)	CU YD	17.5	17.5		
20400800	FURNISHED EXCAVATION	CU YD	615.7	615.7		
20900110	POROUS GRANULAR BACKFILL	CU YD	470	470		
21101615	TOPSOIL FURNISH & PLACE, 4"	SQ YD	10412	10412		
25000210	SEEDING, CLASS 2A	ACRE	2.57	2.57		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	194.3	194.3		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	194.3	194.3		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	194.3	194.3		
25100630	EROSION CONTROL BLANKET	SQ YD	9679	9679		
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	404	404		
28000305	TEMPORARY DITCH CHECKS	FOOT	52	52		

USER NAME = jacobsmr	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 5/10/2019	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	48(B-I)BR(CR)	KNOX	94	3
CONTRACT NO. 68758				
ILLINOIS FED. AID PROJECT				