

MODEL: Default
 FILE NAME: I:\p\lancem\dot\illinois\dot\Documents\DOT_Offices\District_4\Projects\04_68758\CADData\CADsheets\Chestnut\068758-ht-300.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY	BRIDGE	
				0004	0010	
				RURAL	S. N. 048-0095	
				KNOX	KNOX	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	76630		76630	
51201600	FURNISHING STEEL PILES HP 12 X 53	FOOT	310		310	
51201610	FURNISHING STEEL PILES HP 12 X 63	FOOT	320		320	
51202305	DRIVING PILES	FOOT	630		630	
51203600	TEST PILE STEEL HP 12 X 53	EACH	2		2	
51203610	TEST PILE STEEL HP 12 X 63	EACH	2		2	
51500100	NAME PLATES	EACH	2	1	1	
52100505	ANCHOR BOLTS, 5/8"	EACH	24		24	
52100520	ANCHOR BOLTS, 1"	EACH	24		24	
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	1	1		
54003000	CONCRETE BOX CULVERTS	CU YD	6.4	6.4		
54010705	PRECAST CONCRETE BOX CULVERT 7' X 5'	FOOT	102	102		
54260315	TRAVERSABLE PIPE GRATE FOR CONCRETE END SECTION	FOOT	57	57		
54262718	METAL FLARED END SECTIONS 18"	EACH	2	2		

USER NAME = jacobsmr	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 5/10/2019	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	48(B-1)BR(CR)	KNOX	94	7
CONTRACT NO. 68758				
ILLINOIS FED. AID PROJECT				