F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2005-048 L	COOK	85	3
STA. ----+--		TO STA. ----+--		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

60A23

PROJECT: HIGH MAST LIGHT TOWER SERVICE PADS
COOK COUNTY / CITY OF CHICAGO

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	100% STATE
				DAN RYAN Y007
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4681	4681
21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	1510	1510
25000210	SEEDING, CLASS 2A	ACRE	6.50	6.50
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	585	585
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	585	585
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	585	585
25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	0.50	0.50
25100630	EROSION CONTROL BLANKET	SQ YD	33328	33328
25200200	SUPPLEMENTAL WATERING	UNIT	1747	1747
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	700	700
28000300	TEMPORARY DITCH CHECKS	EACH	16	16
28000510	INLET FILTERS	EACH	85	85
50300300	PROTECTIVE COAT	SQ YD	594	594
60600605	CONCRETE CURB, TYPE B	FOOT	132	132
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CALDA	15	15
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	154	154
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	170	170
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	4987	4987
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	1247	1247
X0324433	LIGHT TOWER, SERVICE PAD, 6"	SQ FT	4247	4247
X0324698	APPLY DUST SUPPRESSION AGENTS	UNIT	3	3
X0325132	SHAPING AND GRADING AT HIGH MAST LIGHT TOWER	SQ YD	693	693
X2500322	SEEDING, CLASS 5A (MODIFIED)	ACRE	0.50	0.50
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	12	12

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	06/20/07

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)
I-57 to 71st STREET

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: CBS
DATE: JANUARY 9, 2007 CHECKED BY: TGB