ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

,	F.A.I. RTE.	SECTION	SECTION COUN		TOTAL SHEETS	AL SHEET	
	80/94	2007-031LS	COC	K	51	8	
	STA.		TO STA.	•			
	FED. RO	AD DIST. NO.	ILLINOIS	FED.	AID PROJ	ECT	
	CONTRA	CT NO. 60D14					

Phase I	ľ	WOR	( DATES		
	YEAR	FROM	ТО	CONSTRUCTION WORK	ESTABLISHMENT WORK
	2008	Prior to spring planting		Preparation of designated planting areas for shrubs and free heds	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL HERBICIDE in designated planting areas.
		Thawed soil	April 30	Finish installation of evergreens by April 30.	Apply PRE-EMERGENT GRANULAR HERBICIDE prior to placing mulch.
		Thawed soil	May 15	Finish installation of woody plants by May 15.	Apply PRE-EMERGENT GRANULAR HERBICIDE prior to placing mulch.
Phase I		May 1	May 15	Period of establishment plant care required for woody plants.*	
		May 15	May 31	Period of establishment plant care required for woody plants.*	

<sup>\*</sup> Weeding, watering and other work which is necessary to maintain health and satisfactory appearance of the planting is included in the cost of the contract.

Phase II	[	WOR	K DATES				
	YEAR	FROM	TO	CONSTRUCTION WORK	ESTABLISHMENT WORK		
	2008	June 1		Certification to the Bureau of Maintenance that all woody plants have been installed and are			
				in a live healthy condition and eligible for a September 2008 period of establishment			
				inspection.			
		June 1	June 15	Period of establishment plant care required			
				for woody plants.*			
		June 15	June 30	Period of establishment plant care required			
1				for woody plants.*			
		July 1	July 15	Period of establishment plant care required			
				for woody plants.*			
		July 15	July 31	Period of establishment plant care required			
		ļ		for woody plants.*			
		Aug. 1	Aug. 15	Period of establishment plant care required			
	ļ		1	for woody plants.*			
		Aug. 15	Aug. 31	Period of establishment plant care required			
1				for woody plants.*			
		Sept. 1	Sept. 15	Period of establishment plant care required			
	ł			for woody plants.*			
		Sept. 15	Sept. 30	Period of establishment plant care required			
			0.1.15	for woody plants.*			
	İ	Oct. 1	Oct. 15	Additional watering for woody plants if			
1		0.1.17		required by the Engineer.			
		Oct. 15	Oct. 31	Additional watering for woody plants if			
1			N. 45	required by the Engineer.			
l		Nov. 1	Nov. 15	Additional watering for woody plants if			
				required by the Engineer.			
		Nov. 15	Nov. 30	Additional watering for woody plants if			
				required by the Engineer.			
		Dec. 1	Dec. 15	Additional watering for woody plants if			
			<del> </del>	required by the Engineer.	,		
Di 11		Dec. 15	Dec. 31	Additional watering for woody plants if			
Phase II	L			required by the Engineer.			

<sup>\*</sup> Weeding, watering and other work which is necessary to maintain health and satisfactory appearance of the planting is included in the cost of the contract.

hase III		WORK DATES			
	YEAR	FROM	ТО	CONSTRUCTION WORK	ESTABLISHMENT WORK
	2009	Thawed	May 15		
		Soil		Installation of all required replacement	Apply PRE-EMERGENT GRANULAR
				woody plants, and all required clean up of	HERBICIDE to all replacement woody plants
				woody plants shall be completed by May 15.	prior to placing mulch.
		May 1	May 31		SUPPLEMENTAL WATERING for woody
					plants if required by the Engineer.
		June 1	June 30		SUPPLEMENTAL WATERING for woody
					plants if required by the Engineer.
		July 1	July 31		SUPPLEMENTAL WATERING for woody
					plants if required by the Engineer.
		J	uly 15		Inspection date for WOODY PLANT CARE.
					(Plant care work must be complete and
					acceptable on the inspection date).
		Sept. 1	Sept. 30		SUPPLEMENTAL WATERING for woody
					plants if required by the Engineer.
		Sept	ember 15		Inspection date for WOODY PLANT CARE.
					(Plant care work must be complete and
					acceptable on the inspection date).
		Oct. 1	Oct. 31		SUPPLEMENTAL WATERING for woody
hase III		1			plants if required by the Engineer.

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
LANDSCAPING PLAN
KINGERY EXPRESSWAY I - 80/94
PLANTING CALENDAR
SCALE 1:500
DATE 06/07
CHECKED BY TJW

AMERICAN
CONSULTING ENGINEERS

Contracti sEB LS\_37.rds

11:17:32 AM g:\Project\2014080\CADD\Con