

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	(2HB-2, 2HB-1D)	WINNEBAGO	107	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

URBAN

ITEM CODE	PAY ITEM	UNIT	1000 ROADWAY QUANTITY	X271-2A STRUCTURE QUANTITY	80% FED 20% STATE TOTAL QUANTITY
51100100	SLOPE WALL 4 INCH	SQ YD		2837	2837
51201600	FURNISHING STEEL PILES HP12X53	FOOT		1215	1215
51202305	DRIVING PILES	FOOT		1090	1090
51203600	TEST PILE STEEL HP12X53	EACH		3	3
51500100	NAME PLATES	EACH		4	4
52000110	PREFORMED JOINT STRIP SEAL	FOOT		386	386
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH		24	24
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH		24	24
52100520	ANCHOR BOLTS, 1"	EACH		112	112
58700300	CONCRETE SEALER	SQ FT		6916	6916
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD		216.7	216.7
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT		506	506
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	3312.5		3312.5
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	16		16
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	6		6
63200310	GUARDRAIL REMOVAL	FOOT	3695		3695
* 63600105	DELINEATORS	EACH	6		6
64200105	SHOULDER RUMBLE STRIP	FOOT	3620		3620
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	18		18
67100100	MOBILIZATION	L SUM	1		1
* 70100410	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416	EACH	2		2
* 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	33000		33000
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5500		5500
70400100	TEMPORARY CONCRETE BARRIER	FOOT	5580		5580
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4700		4700
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	700		700
* 78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	5400		5400
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	44		44
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	24		24
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	48		48
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	16		16
* 78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	6		6
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2250		2250
X0323830	DRAINAGE SCUPPER, DS-11	EACH		8	8
* X0113015	TRAFFIC CONTROL FOR ROAD CLOSURES	L SUM	1		1
X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1		1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4		4
Z0030350	RELOCATE IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US 20 OVER
PRAIRIE AND SIMPSON ROADS

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY AJP
HORIZ. CHECKED BY SPF
DATE 06/22/07