

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
220	(23-BR) I	MERCER	50	7
STA. 99+71		TO STA. 109+76		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

BRIDGE APPROACH PAVEMENT			
LOCATION	L (FT)	W (FT)	SQ YD
STA 102+94.29 TO STA 103+24.29	30.0	33.67	112.2
STA 106+23.21 TO STA 106+53.21	30.0	33.67	112.2
TOTAL			224

BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)			
LOCATION	L (FT)	W (FT)	SQ YD
STA 102+88.29 TO STA 102+94.29	6.0	33.67	22.5
STA 106+53.21 TO STA 106+59.21	6.0	33.67	22.5
TOTAL			45

PAVEMENT REMOVAL	
LOCATION	SQ YD
STA 102+94.29 TO STA 103+23.46	91
STA 106+24.04 TO STA 106+53.21	91
TOTAL	182

PAVED SHOULDER REMOVAL	
LOCATION	SQ YD
LT STA 99+71 TO STA 102+94.29	35.9
RT STA 99+71 TO STA 102+94.29	35.9
LT STA 106+53.21 TO STA 109+76	35.9
RT STA 106+53.21 TO STA 109+76	35.9
TOTAL	144

CONCRETE THRUST BLOCKS	
LOCATION	EACH
LT STA 103+10.29	1
RT STA 103+10.29	1
TOTAL	2

STEEL PLATE BEAM GUARDRAIL, TYPE A	
LOCATION	FOOT
LT STA 101+42.81 TO STA 102+92.81	150.0
RT STA 100+55.31 TO STA 102+92.81	237.5
LT STA 106+54.69 TO STA 108+92.19	237.5
RT STA 106+54.69 TO STA 108+04.69	150.0
TOTAL	775

TRAFFIC BARRIER TERMINAL, TYPE 6	
LOCATION	EACH
LT STA 102+92.81 TO STA 103+25.96	1
RT STA 102+92.81 TO STA 103+25.96	1
LT STA 106+21.54 TO STA 106+54.69	1
RT STA 106+21.54 TO STA 106+54.69	1
TOTAL	4

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	
LOCATION	EACH
LT STA 100+92.81 TO STA 101+42.81	1
RT STA 100+05.31 TO STA 100+55.31	1
LT STA 108+92.19 TO STA 109+42.19	1
RT STA 108+04.69 TO STA 108+54.69	1
TOTAL	4

GUARDRAIL REMOVAL	
LOCATION	FOOT
LT STA 101+45.5 TO STA 103+23.5	178
RT STA 100+56.5 TO STA 103+23.5	267
LT STA 106+24 TO STA 108+91	267
RT STA 106+24 TO STA 108+02	178
TOTAL	890

FURNISHING AND ERECTING RIGHT OF WAY MARKERS	
LOCATION	EACH
STA 108+00 65.0' RT	1
STA 107+00 65.0' LT	1
STA 110+00 65.0' RT	1
STA 110+00 65.0' LT	1
STA 111+00 50.0' RT	1
STA 111+00 50.0' LT	1
TOTAL	6

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
SEC. (23-BR) I	6
TOTAL	6

WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
STA 99+71 TO STA 109+76	112
TOTAL	112

PAINT PAVEMENT MARKINGS-LINE 4"	
LOCATION	FOOT
LT STA 99+71 TO STA 109+76 (WHITE)	1005
CTR STA 99+71 TO STA 109+76 (C) (YELLOW)	251
RT STA 99+71 TO STA 109+76 (WHITE)	1005
TOTAL	2261

GUARDRAIL MARKERS, TYPE A	
LOCATION	EACH
RT STA 100+55 TO STA 103+04.67	4
LT STA 101+43 TO STA 103+09.44	3
RT STA 106+37.56 TO STA 108+04	3
LT STA 106+42.33 TO STA 108+92	4
TOTAL	14

GUARDRAIL MARKERS, TYPE C	
LOCATION	EACH
RT. STA. 103+87.89 TO STA. 105+54.33	3
LT. STA. 103+92.67 TO STA. 105+59.11	3
TOTAL	6

TERMINAL MARKERS DIRECT APPLIED	
LOCATION	EACH
RT STA 100+05.31	1
LT STA 100+92.81	1
RT STA 108+54.69	1
LT STA 109+42.19	1
TOTAL	4

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES