

GENERAL NOTES

AVAILABILITY OF ELECTRONIC FILES

MICROSTATION AND GEOPAK FILES OF THIS PROJECT WILL BE MADE AVAILABLE TO THE CONTRACTOR. IF THERE IS A CONFLICT BETWEEN THE ELECTRONIC FILES AND THE PRINTED CONTRACT PLANS AND DOCUMENTS, THE PRINTED CONTRACT PLANS AND DOCUMENTS SHALL TAKE PRECEDENCE OVER THE ELECTRONIC FILES. THE CONTRACTOR SHALL ACCEPT ALL RISK ASSOCIATED WITH USING THE ELECTRONIC FILES AND SHALL HOLD THE DEPARTMENT HARMLESS FOR ANY ERRORS OR OMISSIONS IN THE ELECTRONIC FILES AND THE DATE CONTAINED THEREIN. ERRORS OR DELAYS RESULTING FROM THE USE OF THE ELECTRONIC FILES BY THE CONTRACTOR SHALL NOT RESULT IN ANY EXTENSION OF TIME FOR ANY INTERIM OR FINAL COMPLETION DATE OR SHALL NOT BE CONSIDERED CAUSE FOR ADDITIONAL COMPENSATION. THE CONTRACTOR SHALL NOT USE, SHARE, OR DISTRIBUTE THESE ELECTRONIC FILES EXCEPT FOR THE PURPOSE OF CONSTRUCTING THIS CONTRACT. ANY CLAIMS BY THIRD PARTIES DUE TO USE OR ERRORS SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL INCLUDE THIS DISCLAIMER WITH THE TRANSFER OF THESE ELECTRONIC FILES TO ANY OTHER PARTIES AND SHALL INCLUDE THE APPROPRIATE LANGUAGE BINDING THEM TO SIMILAR RESPONSIBILITIES.

UTILITIES - LOCATIONS/INFORMATION ON PLANS

THE LOCATIONS OF EXISTING WATER MAINS, GAS MAINS, SEWERS, ELECTRIC POWER LINES, TELEPHONE LINES AND OTHER UTILITIES AS SHOWN ON THE PLANS ARE BASED ON CAREFUL FIELD INVESTIGATION AND THE BEST INFORMATION AVAILABLE, BUT THEY ARE NOT GUARANTEED. UNLESS ELEVATIONS ARE SHOWN - ALL UTILITY LOCATIONS SHOWN ON THE CROSS SECTIONS ARE BASED ON THE APPROXIMATE DEPTH SUPPLIED BY THE UTILITY COMPANY. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ASCERTAIN THEIR EXACT LOCATION FROM THE UTILITY COMPANIES AND BY FIELD INSPECTION.

PLAN ELEVATIONS - U.S.G.S. MEAN SEA LEVEL DATUM

ALL ELEVATIONS SHOWN ON THE PLANS ARE ESTABLISHED FROM U.S.G.S. MEAN SEA LEVEL DATUM.

TREE REMOVAL

THE DISTRICT FOUR TREE COMMITTEE SHOULD BE CONTACTED AND PRIOR APPROVAL OBTAINED FOR ANY TREE REMOVAL BEYOND THE LIMITS/LOCATIONS INCLUDED IN THE PLANS.

ENVIRONMENTAL REVIEWS

PRIOR TO THE USE OF ANY PROPOSED BORROW AREAS, USE AREAS (TEMPORARY ACCESS ROADS, DETOURS, RUN-AROUNDS, ETC.) AND/OR WASTE AREAS, THE CONTRACTOR SHALL FILE THE REQUIRED ENVIRONMENTAL RESOURCE REQUEST SURVEYS ACCORDING TO SECTION 107.22 OF THE STANDARD SPECIFICATIONS. THESE SURVEYS ARE REQUIRED IN ORDER FOR THE DEPARTMENT TO CONDUCT CULTURAL AND BIOLOGICAL RESOURCE SURVEYS FOR THE PROPOSED SITE.

PRIOR TO ANY WASTE MATERIALS BEING REMOVED FROM THE CONSTRUCTION SITE THE REQUIRED ENVIRONMENTAL RESOURCE SURVEYS WILL NEED TO BE OBTAINED AND FILED BY THE CONTRACTOR. EXCESS WASTE PRODUCTS REMOVED FROM THE CONSTRUCTION SITE SHALL BE DISPOSED OF AS REQUIRED IN SECTION 202.03 OF THE STANDARD SPECIFICATIONS.

ANY PROTRUDING METAL BARS SHALL BE REMOVED PRIOR TO THE DISPOSAL OF BROKEN CONCRETE AT APPROVED DISPOSAL SITES.

THE REQUIRED ENVIRONMENTAL RESOURCE DOCUMENTATION SHALL INCLUDE THE FOLLOWING:

- BDE FORM 2289 (ENVIRONMENTAL SURVEY REQUEST)
- A LOCATION MAP SHOWING THE SIZE LIMITS AND LOCATION OF THE USE AREA
- SIGNED PROPERTY OWNER AGREEMENT FORM - D4 P10100
- COLOR PHOTOGRAPHS DEPICTING THE USE AREA.
- BORROW AREA ENTRY AGREEMENT FORM - D4 P10101

PLEASE NOTE THAT A MINIMUM OF TWO WEEKS SHALL BE ALLOWED FOR THE DISTRICT TO OBTAIN THE REQUIRED ENVIRONMENTAL CLEARANCES.

ORDERING LENGTH CONFIRMATION - DRAINAGE ITEMS

THE CONTRACTOR SHALL CONSULT WITH THE ENGINEER IN REGARD TO THE EXACT LENGTH OF THE BOX/PIPE CULVERTS, STORM SEWERS, AND/OR PIPE DRAINS REQUIRED PRIOR TO ORDERING THESE ITEMS.

EXISTING DRAINAGE PIPES CONNECTED TO NEW STRUCTURES

IN ACCORDANCE WITH SECTION 602 OF THE STANDARD SPECIFICATIONS, THE CONNECTING OF EXISTING DRAIN TILES, PIPE CULVERTS, OR STORM SEWERS TO THE PROPOSED DRAINAGE SYSTEM STRUCTURES WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED AS INCLUDED IN THE PAY ITEMS PROVIDED.

ENGINEERS FIELD OFFICE

ALL OF THE TELEPHONE LINES PROVIDED SHALL HAVE UNPUBLISHED NUMBERS.

COMMITMENTS

COMMITMENTS ARE NOT TO BE ALTERED WITHOUT THE WRITTEN PERMISSION OF ALL PARTIES TO WHICH THE COMMITMENT WAS MADE.

NO COMMITMENTS HAVE BEEN INCURRED ON THIS PROJECT.

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX, GENERAL NOTES & COMMITMENTS
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTIONS
5	SCHEDULES OF QUANTITIES
6	ALIGNMENT, TIES & BENCHMARKS
7	GENERAL PLAN & ELEVATION 1
8	GENERAL PLAN & ELEVATION 2
9	GENERAL PLAN & ELEVATION 3
10	TRAFFIC CONTROL AND PROTECTION (SPECIAL)
11	EROSION CONTROL PLAN
12	DRAINAGE & GRADING PLAN
13	TEMPORARY EASEMENT PLAN
14	LANDSCAPING PLAN
15	STRUCTURAL NOTES
16	PANEL DETAILS
17	PANEL DATA
18	POST DETAILS 1
19	POST DETAILS 2
20	POST DATA
21	SHAFT DETAILS
22	SOIL BORINGS
23	SOIL BORINGS
24	SOIL BORINGS
25	SOIL BORINGS
26	SOIL BORINGS
27	SOIL BORINGS
28	SOIL BORINGS
29	DISTRICT 4 STANDARD 205001-D4
30	DISTRICT 4 STANDARD 542016-D4
31	CROSS SECTIONS
32	CROSS SECTIONS
33	CROSS SECTIONS
34	CROSS SECTIONS
35	CROSS SECTIONS
36	CROSS SECTIONS
37	CROSS SECTIONS
38	HIGHWAY STANDARD 280001-03 (1 OF 2)
39	HIGHWAY STANDARD 280001-03 (2 OF 2)
40	HIGHWAY STANDARD 542301-01
41	HIGHWAY STANDARD 602401-01
42	HIGHWAY STANDARD 604001-02
43	HIGHWAY STANDARD 664001-01 (1 OF 3)
44	HIGHWAY STANDARD 664001-01 (2 OF 3)
45	HIGHWAY STANDARD 664001-01 (3 OF 3)

DISTRICT STANDARDS

STANDARD NO.	DESCRIPTION
205001-D4	SLOPE STEPS DETAIL
542016-D4	PIPE CULVERT EXTENSION COLLAR (WITHOUT END SECTION)

HIGHWAY STANDARDS

STANDARD NO.	DESCRIPTION
280001-03	TEMPORARY EROSION CONTROL SYSTEMS
542301-01	PRECAST REINFORCED CONCRETE FLARED END SECTION
602401-01	MANHOLE TYPE A
604001-02	FRAME AND LIDS TYPE 1
664001-01	CHAIN LINKED FENCE

ROUTE NO.	SECTION	COUNTY	SHEET	SHEET NO. 2
F.A.I. I-74	*	Peoria	2	15 SHEETS
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

Contract # 68736 * D4 I-74 Noise Wall 2008

REVISIONS	
NAME	DATE

benesch

alfred benesch & company
 Engineers • Surveyors • Planners
 225 North Michigan Avenue, Suite 2400
 Chicago, Illinois 60601
 312-565-0450
 JOB NO. 3573

ILLINOIS DEPARTMENT OF TRANSPORTATION
INDEX, GENERAL NOTES & COMMITMENTS
 NOISE ABATEMENT WALL
 F.A.I. RTE. 74 (I-74)
 SECTION D4 I-74 NOISE WALL 2008
 PEORIA COUNTY
 STA. 142+916.64 TO STA. 143+287.69
 STRUCTURE NUMBER 072-8554

6/20/2007 4:15:10 PM c:\projects\dot\03513\noise\wall2\plans\3573nw_index.dgn