

SUMMARY OF QUANTITIES				URBAN		
				IM		
				90% FED 10% STATE		
				CONSTRUCTION TYPE CODE		
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	NOISE WALLS Y220		
51500100	NAME PLATES	EACH	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	60	60		
M2040800	FURNISHED EXCAVATION	CU M	1,485	1,485		
M2113100	TOPSOIL FURNISH AND PLACE, 100MM	SO M	1,080	1,080		
M2500200	SEEDING, CLASS 2	HA	0.2	0.2		
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	22.3	22.3		
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	22.3	22.3		
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	22.3	22.3		
M2510115	MULCH, METHOD 2	HA	0.2	0.2		
M2800400	PERIMETER EROSION BARRIER	METER	407	407		
M2810807	STONE DUMPED RIPRAP, CLASS A4	M TON	22	22		
M2820200	FILTER FABRIC	SO M	30	30		
M5429910	CONCRETE COLLAR	CU M	0.5	0.5		
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTION 600MM	EACH	1	1		
M5500420	STORM SEWERS, CLASS A, TYPE 2, 200MM	METER	6.0	6.0		
M5500465	STORM SEWERS, CLASS A, TYPE 2, 600MM	METER	6.0	6.0		
M5503090	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 600MM	METER	20.0	20.0		
M6021605	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1		
M6640100	CHAIN LINK FENCE, 1.2 METER	METER	8	8		
M6641920	CHAIN LINK FENCE REMOVAL	METER	285	285		
MX030126	NOISE ABATEMENT WALL, GROUND MOUNTED (PRECAST CONCRETE)	SO M	1,772	1,772		
X2010510	CLEARING AND GRUBBING	L SUM	1	1		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		

6/20/2007 4:55:11 PM o:\projects\data\3573\noisewalls\walla2\plans\3573nw_bom.dgn

benesch
 alfred benesch & company
 Engineers - Surveyors - Planners
 205 North Michigan Avenue, Suite 2400
 Chicago, Illinois 60601
 312-566-0450
 JOB NO. 3573

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 NOISE ABATEMENT WALL
 F.A.I. RTE. 74 (I-74)
 SECTION D4 I-74 NOISE WALL 2008
 PEORIA COUNTY
 STA. 142+916.64 TO STA. 143+287.69
 STRUCTURE NUMBER 072-8554