

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6711	00-00164-00-SP	TAZEWELL	80	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

**20100110 TREE REMOVAL (6 TO 25 UNITS IN DIAMETER)**

LOCATION	LT	UNIT	REMARKS
28+56.00		12.0	
28+56.00	LT	10.0	
28+56.00	LT	9.1	
28+56.00	LT	11.3	
28+56.00	LT	10.7	
34+35.00	LT	11.1	
34+80.65	LT	5.3	
35+17.20	LT	12.9	
35+52.65	LT	4.6	
88+59.84	LT	14.3	
88+87.33	LT	9.5	
TOTAL: 111			

**20100210 TREE REMOVAL (OVER 15 UNITS IN DIAMETER)**

LOCATION	LT	UNIT	REMARKS
28+88.75		27.9	
TOTAL: 28			

**20800150 TRENCH BACKFILL**

LOCATION	RT	CU YD	REMARKS
90+51.25 TO 90+63.75	RT	33.3	STORM SEWER SS-4
32+95.00 TO 89+53.00	LT	13.6	STORM SEWER SS-7
90+63.29 TO 90+63.75	RT	3.2	STORM SEWER SS-3
89+52.86 TO 89+53.00	LT	15.6	STORM SEWER SS-8
36+16.47 TO 36+25.00	AR	13.8	STORM SEWER SS-11
38+31.20 TO 38+50.55	AR	73.1	STORM SEWER SS-15
88+15.25 TO 88+21.50	LT	4.2	STORM SEWER SS-9
88+38.50 TO 88+21.50	RT	11.5	STORM SEWER SS-10
92+43.88 TO 92+43.75	LT	3.6	STORM SEWER SS-1
TOTAL: 172			

**21101615 TOPSOIL, FURNISH AND PLACE 4"**

LOCATION	TO	FROM	LT	RT	SQ YD	REMARKS
26+80.00	TO	32+00.00			739.4	
32+00.00	TO	37+50.00			490.3	
37+50.00	TO	40+14.00			195.6	
86+68.36	TO	89+00.00			8.3	
91+00.00	TO	93+00.00			183.3	
TOTAL: 1617						

**25200110 SODDING, SALT TOLERANT**

LOCATION	TO	FROM	LT	RT	SQ YD	REMARKS
26+80.00	TO	32+00.00			698.3	
32+00.00	TO	37+50.00			490.3	
37+50.00	TO	40+14.00			195.6	
86+68.36	TO	89+00.00			8.3	
91+00.00	TO	93+00.00			183.3	
TOTAL: 1576						

**28000400 PERIMETER EROSION BARRIER**

LOCATION	TO	FROM	LT	RT	FOOT	REMARKS
26+80.00	TO	29+97.00	LT		355.0	
91+00.00	TO	92+60.00	LT		164.0	
TOTAL: 519						

**28000500 INLET AND PIPE PROTECTION**

LOCATION	RT	LT	EACH	REMARKS
27+84	RT		1	STRUCTURE FES-3
29+52	RT		1	STRUCTURE IN-17
90+51	RT		1	STRUCTURE IN-4
32+11	RT		1	STRUCTURE IN-5
89+53	LT		1	STRUCTURE IN-8
TOTAL: 5				

**31100300 SUBBASE GRANULAR MATERIAL, TYPE A, 4"**

LOCATION	TO	FROM	LT	RT	SQ YD	REMARKS
26+80.00	TO	32+00.00			1040.2	
32+00.00	TO	37+50.00			1535.4	
37+50.00	TO	40+14.00			477.9	
86+68.36	TO	89+00.00			549.4	
91+00.00	TO	93+00.00			359.4	
TOTAL: 3962						

**35101400 AGGREGATE BASE COURSE, TYPE B**

LOCATION	TO	FROM	LT	RT	TONS	REMARKS
29+79.10	TO	30+00.75			91.2	6" PARKING LOT
30+24.82	TO	31+01.73			51.8	8" ENT TY 1 30+65.00 LT
31+56.77	TO	32+21.95			42.3	8" CE 31+96.10 LT
34+92.30	TO	35+64.11			34.3	8" ENT TY 1 35+28.30 RT
35+62.14	TO	36+14.25			30.2	8" ENT TY 1 35+87.80 LT
35+71.20	TO	36+60.77			72.8	8" ENT TY 1 36+17.16 RT
36+20.21	TO	36+77.52			16.9	8" ENT TY 1 36+48.00 LT
36+88.78	TO	37+41.27			29.1	8" CE 37+15.00 RT
37+07.07	TO	37+75.87			18.9	8" ENT TY 1 37+38.00 LT
38+16.75	TO	38+62.46			14.9	8" ENT TY 1 38+40.60 LT
38+46.80	TO	39+00.73			28.2	8" CE 38+74.30 RT
39+10.90	TO	39+80.00			43.0	8" ENT TY 2 39+45.90 LT
40+88.15	TO	41+42.01			30.9	8" ENT TY 2 41+15.00 LT
87+22.37	TO	87+67.80			43.1	8" ENT TY 1 87+50.00 RT
87+67.80	TO	88+31.30			20.9	8" ENT TY 1 88+00.00 RT
88+23.05	TO	88+66.89			22.9	8" ENT TY 1 88+45.00 LT
TOTAL: 591						

**35300300 PORTLAND CEMENT CONCRETE BASE COURSE 8"**

LOCATION	TO	FROM	LT	RT	SQ YD	REMARKS
28+48.71	TO	32+00.00			505.1	
32+00.00	TO	37+50.00			1020.1	
37+50.00	TO	38+43.82			93.8	
87+62.81	TO	89+00.00			319.0	
91+00.00	TO	92+38.57			144.1	
TOTAL: 2082						

**35400300 PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"**

LOCATION	TO	FROM	LT	RT	SQ YD	REMARKS
26+90.82	TO	29+24.79			199.3	
32+60.25	TO	37+35.07			95.6	
37+97.31	TO	40+13.95			174.8	
87+19.47	TO	87+45.70			53.9	
92+38.57	TO	92+94.55			56.6	
TOTAL: 580						

**40600100 BITUMINOUS MATERIALS (PRIME COAT)**

LOCATION	TO	FROM	LT	RT	GALLONS	REMARKS
26+80.00	TO	32+00.00			323.3	
32+00.00	TO	37+50.00			564.8	
37+50.00	TO	40+14.00			148.9	
86+68.36	TO	89+00.00			185.7	
91+00.00	TO	93+00.00			136.2	
TOTAL: 1359						

**40600300 AGGREGATE (PRIME COAT)**

LOCATION	TO	FROM	LT	RT	TONS	REMARKS
26+80.00	TO	32+00.00			6.5	
32+00.00	TO	37+50.00			11.3	
37+50.00	TO	40+14.00			3.0	
86+68.36	TO	89+00.00			3.7	
91+00.00	TO	93+00.00			2.7	
TOTAL: 27						

**40600625 LEVELING BINDER (MACHINE METHOD), N50**

LOCATION	TO	FROM	LT	RT	TONS	REMARKS
26+80.00	TO	32+00.00			113.1	
32+00.00	TO	37+50.00			371.7	
38+00.00	TO	40+00.00			138.0	
86+68.36	TO	89+00.00			30.6	
91+00.00	TO	93+00.00			6.3	
TOTAL: 660						

**40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT**

LOCATION	TO	FROM	LT	RT	SQ YD	REMARKS
26+80.00	TO	26+90.00	AR		46.9	SOUTH END OF PARKWAY DRIVE
40+04.00	TO	40+14.00	AR		47.6	NORTH END OF PARKWAY DRIVE
86+68.36	TO	86+78.36	AR		60.5	WEST END OF BROADWAY ROAD
86+90.84	TO	87+18.61	LT		30.9	ARROW ROAD
92+90.00	TO	93+00.00	AR		58.0	EAST END OF BROADWAY ROAD
TOTAL: 244						

**40600990 TEMPORARY RAMP**

LOCATION	TO	FROM	LT	RT	SQ YD	REMARKS
26+80.00	TO	26+90.00	AR		31.3	SOUTH END OF PARKWAY DRIVE
40+04.00	TO	40+14.00	AR		31.7	NORTH END OF PARKWAY DRIVE
86+68.36	TO	86+78.36	AR		40.4	WEST END OF BROADWAY ROAD
86+90.84	TO	87+18.61	LT		20.6	ARROW ROAD
92+90.00	TO	93+00.00	AR		38.7	EAST END OF BROADWAY ROAD
TOTAL: 163						

**40603560 POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N50**

LOCATION	TO	FROM	LT	RT	TONS	REMARKS
26+80.00	TO	32+00.00			281.9	
32+00.00	TO	37+50.00			491.4	
37+50.00	TO	40+14.00			130.5	
86+68.36	TO	89+00.00			161.6	
91+00.00	TO	93+00.00			119.4	
TOTAL: 1185						

**40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING**

LOCATION	TO	FROM	LT	RT	TON	REMARKS
29+79.10	TO	30+00.75	LT		44.8	MONICAL'S PARKING LOT
34+86.47	TO	35+50.63	RT		29.0	BANK ENTRANCE
36+97.27	TO	37+38.55	RT		3.2	PARKING LOT
37+91.95	TO	38+12.16	RT		3.4	PARKING LOT
38+59.00	TO	38+87.00	RT		8.6	PARKING LOT
86+68.36	TO	87+29.76	RT		8.6	BROADWAY LIQUORS PARKING LOT
TOTAL: 98						

**42300200 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH**

LOCATION	TO	FROM	LT	RT	SQ FT	REMARKS
30+26.27	TO	31+03.18			113.6	ENT TY 1 LT STA 30+65.00
31+56.77	TO	32+21.95			92.7	CE LT STA 31+96.10
34+92.30	TO	35+64.11			75.2	ENT TY 1 RT STA 35+28.30
35+56.14	TO	36+12.60			66.2	ENT TY 1 LT STA 35+86.00
35+71.20	TO	36+60.77			159.7	ENT TY 1 RT STA 36+18.60
36+20.21	TO	36+77.52			37.1	ENT TY 1 LT STA 36+48.00
36+88.78	TO	37+41.27			63.8	CE RT STA 37+15.00
36+99.46	TO	37+75.87			41.4	ENT TY 1 LT STA 37+38.00
38+16.75	TO	38+62.46			32.7	ENT TY 1 LT STA 38+42.00
38+46.80	TO	39+00.73			61.9	CE RT STA 38+74.30
39+10.89	TO	39+80.00			94.2	ENT TY 2 LT STA 39+47.39
40+88.15	TO	41+42.01			67.8	ENT TY 2 LT STA 41+15.00
87+22.37	TO	87+67.80			94.6	ENT TY 1 RT STA 87+50.00
87+67.80	TO	88+31.30			45.8	ENT TY 1 RT STA 88+00.00
88+23.05	TO	88+66.89			50.3	ENT TY 1 LT STA 88+45.00
TOTAL: 1097						

