

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6711	00-00164-00-SP	TAZEWELL	80	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

550A0090 STORM SEWERS, CLASS A, TYPE 1 18"

LOCATION	EQOIT	REMARKS
MH-4 TO HW-1	3.0	STORM SEWER SS-19
TOTAL: 3		

550A0340 STORM SEWERS, CLASS A, TYPE 2 12"

LOCATION	EQOIT	REMARKS
IN-9 TO MH-2	48.9	STORM SEWER SS-8
TOTAL: 49		

550A0380 STORM SEWERS, CLASS A, TYPE 2 18"

LOCATION	EQOIT	REMARKS
EX TO MH-4	33.0	STORM SEWER SS-17
TOTAL: 33		

550A0410 STORM SEWERS, CLASS A, TYPE 2 24"

LOCATION	EQOIT	REMARKS
IN-15 TO IN-16	57.5	STORM SEWER SS-15
IN-16 TO DS(S)	330.4	STORM SEWER SS-16
TOTAL: 388		

60218400 MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID

LOCATION	EACH	REMARKS
29+16.59	1	STRUCTURE MH-4
92+43.75	1	STRUCTURE MH-5
TOTAL: 2		

60221100 MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID

LOCATION	EACH	REMARKS
89+53.00	1	STRUCTURE MH-2
88+21.50	1	STRUCTURE MH-3
TOTAL: 2		

60234200 INLETS, TYPE A, TYPE 1 FRAME, OPEN LID

LOCATION	EACH	REMARKS
36+85.00	1	STRUCTURE IN-13
37+95.00	1	STRUCTURE IN-14
TOTAL: 2		

60241800 INLETS, TYPE G-1

LOCATION	EACH	REMARKS
90+63.29	1	STRUCTURE IN-3 (VANED LEFT)
32+31.67	1	STRUCTURE IN-6 (DIAGONAL)
32+95.00	1	STRUCTURE IN-7 (DIAGONAL)
89+52.86	1	STRUCTURE IN-8 (DIAGONAL)
88+15.25	1	STRUCTURE IN-9 (VANED LEFT)
88+38.50	1	STRUCTURE IN-10 (VANED RIGHT)
36+16.47	1	STRUCTURE IN-11 (DIAGONAL)
36+69.52	1	STRUCTURE IN-12 (DIAGONAL)
TOTAL: 8		

60255500 MANHOLES TO BE ADJUSTED

LOCATION	EACH	REMARKS
31+16.93	1	SANITARY MANHOLE
33+84.56	1	STORM SEWER MANHOLE
37+63.04	1	SANITARY MANHOLE
TOTAL: 3		

60262800 INLETS TO BE RECONSTRUCTED (SPECIAL)

LOCATION	EACH	REMARKS
34+12.39	1	RECONSTRUCT WITH FLAT STEEL TOP
TOTAL: 1		

60500060 REMOVING INLETS

LOCATION	EACH	REMARKS
32+89.79	1	EXISTING CURB INLET
TOTAL: 1		

60500065 REMOVING INLETS, SPECIAL

LOCATION	EACH	REMARKS
29+54.40	1	EXISTING DOUBLE INLET
TOTAL: 1		

60600605 CONCRETE CURB, TYPE B

LOCATION	EQOIT	REMARKS
32+54.87 TO 33+00.00	50.0	LT
33+10.87 TO 33+14.42	12.1	LT
88+62.65 TO 89+00.00	37.6	RT
TOTAL: 99.5		

60603800 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12

LOCATION	EQOIT	REMARKS
31+67.33 TO 31+79.62	27.0	ENTRANCE STA 31+96.10
32+12.58 TO 32+25.08	32.5	ENTRANCE STA 31+96.10
36+85.76 TO 37+02.46	43.9	ENTRANCE STA 37+15.00
37+28.52 TO 37+44.38	44.4	ENTRANCE STA 37+15.00
38+43.75 TO 38+60.28	57.6	ENTRANCE STA 38+74.30
38+88.36 TO 39+03.96	53.1	ENTRANCE STA 38+74.30
91+43.84 TO 91+50.00	6.2	HERGET BANK PARKING LOT
91+50.00 TO 92+00.00	50.0	HERGET BANK PARKING LOT
92+00.00 TO 92+26.71	26.7	HERGET BANK PARKING LOT
TOTAL: 341.5		

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

LOCATION	EQOIT	REMARKS
26+80.07 TO 32+00.00	519.9	LT
26+80.07 TO 32+00.00	519.9	RT
32+00.00 TO 33+23.81	160.4	LT
34+03.14 TO 37+50.00	384.3	LT
32+00.00 TO 33+37.11	170.3	RT
34+04.88 TO 37+50.00	390.3	RT
37+50.00 TO 40+14.00	264.0	LT
37+50.00 TO 40+14.00	264.0	RT
87+18.57 TO 89+00.00	150.0	LT
86+68.36 TO 89+00.00	232.0	RT
91+00.00 TO 93+18.45	180.1	LT
91+00.00 TO 93+00.00	200.2	RT
TOTAL: 3435.5		

67100100 MOBILIZATION

LOCATION	L SUM	REMARKS
ENTIRE JOBSITE	1	
TOTAL: 1		

70102625 TRAFFIC CONTROL AND PROTECTION STANDARD 701606

LOCATION	L SUM	REMARKS
ENTIRE JOBSITE	1	
TOTAL: 1		

70102632 TRAFFIC CONTROL AND PROTECTION STANDARD 701602

LOCATION	L SUM	REMARKS
ENTIRE JOBSITE	1	
TOTAL: 1		

70102635 TRAFFIC CONTROL AND PROTECTION STANDARD 701701

LOCATION	L SUM	REMARKS
ENTIRE JOBSITE	1	
TOTAL: 1		

70102640 TRAFFIC CONTROL AND PROTECTION STANDARD 701801

LOCATION	L SUM	REMARKS
ENTIRE JOBSITE	1	
TOTAL: 1		

70300100 SHORT TERM PAVEMENT MARKING

LOCATION	EQOIT	REMARKS
26+80.00 TO 32+00.00	202.8	
32+00.00 TO 37+50.00	475.6	
37+50.00 TO 40+14.00	100.6	
86+70.00 TO 89+00.00	90.4	
91+00.00 TO 93+00.00	75.0	
TOTAL: 944		

70300210 TEMPORARY PAVEMENT MARKINGS - LETTERS AND SYMBOLS

78000100 THERMOPLASTIC PAVEMENT MARKINGS - LETTERS AND SYMBOLS

LOCATION	CL	RT	EQOIT	REMARKS
31+52.00			8.8	WHITE LT ARROW - URBAN
33+02.00			14.7	WHITE RT/TH ARROW - URBAN
33+02.00			8.8	WHITE LT ARROW - URBAN
33+02.00			14.7	WHITE RT/TH ARROW - URBAN
34+50.00			8.8	WHITE RT ARROW - URBAN
34+50.00			8.8	WHITE LT ARROW - URBAN
35+50.00			8.8	WHITE RT ARROW - URBAN
35+50.00			8.8	WHITE LT ARROW - URBAN
89+13.50			8.8	WHITE LT ARROW - URBAN
89+15.00			8.8	WHITE RT ARROW - URBAN
90+80.00			14.7	WHITE RT ARROW - URBAN
90+80.00			8.8	WHITE LT ARROW - URBAN
88+36.00			8.8	WHITE RT/TH ARROW - URBAN
88+40.00			8.8	WHITE LT ARROW - URBAN
91+80.00			14.7	WHITE RT/TH ARROW - URBAN
91+80.00			8.8	WHITE LT ARROW - URBAN
TOTAL: 164				

70300220 TEMPORARY PAVEMENT MARKING - 4"

78000200 THERMOPLASTIC PAVEMENT MARKING - 4"

LOCATION	EQOIT	REMARKS
26+80.00 TO 32+00.00	130.0	WHITE SKIP DASH LINE
31+30.00 TO 32+00.00	73.2	WHITE LANE LINE
31+30.00 TO 32+00.00	73.2	WHITE LANE LINE
26+80.00 TO 32+00.00	130.0	WHITE SKIP DASH LINE
32+00.00 TO 33+30.00	32.5	WHITE SKIP DASH LINE
32+00.00 TO 33+30.00	130.0	WHITE LANE LINE
32+00.00 TO 33+30.00	130.0	WHITE LANE LINE
32+00.00 TO 33+30.00	32.5	WHITE SKIP DASH LINE
34+24.00 TO 37+50.00	81.5	WHITE SKIP DASH LINE
34+24.00 TO 35+62.00	141.2	WHITE LANE LINE
34+24.00 TO 35+62.00	141.2	WHITE LANE LINE
34+24.00 TO 37+50.00	81.5	WHITE SKIP DASH LINE
37+50.00 TO 40+14.00	66.0	WHITE SKIP DASH LINE
37+50.00 TO 40+14.00	66.0	WHITE SKIP DASH LINE
86+68.36 TO 89+42.75	68.6	WHITE SKIP DASH LINE
88+24.75 TO 89+42.75	121.2	WHITE LANE LINE
88+24.75 TO 89+42.75	121.2	WHITE LANE LINE
86+68.36 TO 89+42.75	68.6	WHITE SKIP DASH LINE
90+52.00 TO 91+00.00	12.0	WHITE SKIP DASH LINE
90+52.00 TO 91+00.00	48.0	WHITE LANE LINE
90+52.00 TO 91+00.00	48.0	WHITE LANE LINE
90+52.00 TO 91+00.00	12.0	WHITE SKIP DASH LINE
91+00.00 TO 93+00.00	50.0	WHITE SKIP DASH LINE
91+00.00 TO 92+00.00	103.2	WHITE LANE LINE
91+00.00 TO 92+00.00	103.2	WHITE LANE LINE
91+00.00 TO 93+00.00	50.0	WHITE SKIP DASH LINE
WHITE SUBTOTAL: 2114.8		

