

| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|----------------|----------|------------------|-----------|
| 6711 | 00-00164-00-SP | TAZEWELL | 80 | 11 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

EARTHWORK SCHEDULE

| LOCATION | | 20200100 EARTH EXCAVATION (CUT) | EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) | EMBANKMENT (FILL) | EARTHWORK BALANCE WASTE (SHORTAGE) |
|----------------------|----------|---------------------------------|---|-------------------|------------------------------------|
| FROM | TO | CU YD | CU YD | CU YD | CU YD |
| Parkway Drive | | | | | |
| 27+00.00 | 32+00.00 | 341.8 | 256.3 | 197.2 | 59.1 |
| 32+00.00 | 37+50.00 | 911.9 | 683.9 | 7.7 | 676.2 |
| 37+50.00 | 40+14.00 | 354.3 | 265.7 | 3.0 | 262.7 |
| Broadway Road | | | | | |
| 87+00.00 | 89+50.00 | 302.0 | 226.5 | 0.0 | 226.5 |
| 90+00.00 | 93+00.00 | 123.8 | 92.8 | 29.3 | 63.6 |
| Parking Lot | | | | | |
| 29+79.10 | 30+00.75 | 66.7 | 50.0 | 0.0 | 50.0 |
| Entrances | | | | | |
| 30+26.27 | 31+03.18 | 4.7 | 3.6 | 0.0 | 3.6 |
| 31+56.77 | 32+21.95 | 3.9 | 2.9 | 0.0 | 2.9 |
| 34+92.30 | 35+64.11 | 3.1 | 2.4 | 0.0 | 2.4 |
| 35+62.14 | 36+14.25 | 2.8 | 2.1 | 0.0 | 2.1 |
| 35+71.20 | 36+60.77 | | | | |
| 36+20.21 | 36+77.52 | 1.5 | 1.2 | 0.0 | 1.2 |
| 36+88.78 | 37+41.27 | 2.7 | 2.0 | 0.0 | 2.0 |
| 36+99.46 | 37+75.87 | 1.7 | 1.3 | 0.0 | 1.3 |
| 38+16.75 | 38+62.46 | 1.4 | 1.0 | 0.0 | 1.0 |
| 38+46.80 | 39+00.73 | 2.6 | 1.9 | 0.0 | 1.9 |
| 39+10.90 | 39+80.00 | 3.9 | 2.9 | 0.0 | 2.9 |
| 40+88.15 | 41+42.01 | 2.8 | 2.1 | 0.0 | 2.1 |
| 87+22.37 | 87+67.80 | 3.9 | 3.0 | 0.0 | 3.0 |
| 87+67.80 | 88+31.30 | 1.9 | 1.4 | 0.0 | 1.4 |
| 88+23.05 | 88+66.89 | 2.1 | 1.6 | 0.0 | 1.6 |
| TOTALS | | 2135 | 1601 | 237 | 1364 |
| | | 20200100 EARTH EXCAVATION | | | |
| | | 2135 CU YD | | | |

ENTRANCE SCHEDULE

| LOCATION | REMARKS | LENGTH | WIDTH | PCC DRIVEWAY PAVEMENT 6" SQ YD | EARTH EXCAVATION CU YD | 8" AGG BASE COURSE TYPE B TON |
|-------------------------------------|----------|----------|-------|--------------------------------|------------------------|-------------------------------|
| | | | | 42300200 | 20200110 | 35101400 |
| Construction Details Sheet 1 | | | | | | |
| LT STA | 30+65.00 | ENT TY 1 | 19.5 | 35.0 | 113.6 | 4.7 |
| LT STA | 31+96.10 | CE | 21.9 | 33.0 | 92.7 | 3.9 |
| Construction Details Sheet 2 | | | | | | |
| RT STA | 35+28.30 | ENT TY 1 | 12.0 | 35.0 | 75.2 | 3.1 |
| LT STA | 35+86.00 | ENT TY 1 | 17.2 | 20.0 | 66.2 | 2.8 |
| RT STA | 36+18.60 | ENT TY 1 | 26.3 | 24.0 | 159.7 | 6.7 |
| LT STA | 36+48.00 | ENT TY 1 | 7.9 | 20.5 | 37.1 | 1.5 |
| RT STA | 37+15.00 | CE | 14.5 | 25.0 | 63.8 | 2.7 |
| LT STA | 37+38.00 | ENT TY 1 | 7.1 | 35.0 | 41.4 | 1.7 |
| Construction Details Sheet 3 | | | | | | |
| LT STA | 38+42.00 | ENT TY 1 | 8.9 | 28.0 | 32.7 | 1.4 |
| RT STA | 38+74.30 | CE | 13.5 | 28.0 | 61.9 | 2.6 |
| LT STA | 39+47.39 | ENT TY 2 | 15.3 | 28.0 | 94.2 | 3.9 |
| LT STA | 41+15.00 | ENT TY 2 | 12.5 | 24.0 | 67.8 | 2.8 |
| Construction Details Sheet 4 | | | | | | |
| RT STA | 87+50.00 | ENT TY 1 | 12.0 | 35.0 | 94.6 | 3.9 |
| RT STA | 88+00.00 | ENT TY 1 | 17.3 | 30.0 | 45.8 | 1.9 |
| LT STA | 88+45.00 | ENT TY 1 | 16.0 | 19.0 | 50.3 | 2.1 |

NOTE: QUANTITIES INCLUDED IN INDIVIDUAL PAY ITEM SCHEDULES

