CONTRACT NO. 89318

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6711	00-00164-00-SP	TAZEWELL	80	16
STA. 32+00.00	TO STA. 37+50.00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SWC REAL ESTATE, LLC

MATCH LINE STA 89+25.00
SEE ROADWAY PLAN AND PROFILE SHEET 4

JAMES W. FARREL

DTHC PROPERTIES

BELVA M. HEITZMAN

MATCH LINE STA. 32+00.00
SEE ROADWAY PLAN AND PROFILE SHEET 1

EXIST R.O.W.

PROP R.O.W.

SIDEWALK REMOVAL

PAVEMENT REMOVAL

APPROXIMATE LIMIT HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH) AS REQ'D TO REESTABLISH CROSS SLOPE

TREE REMOVAL

BROADWAY ROAD

PARKWAY STA. 33+71.00 =
BROADWAY STA. 90+00.00

P.I. STA. 35+64.00
179° 0' 0"

32+00 33+00 34+00 35+00 36+00 37+00

90+00

EXISTING STORM MANHOLE
STA 33+84.56 - 31.16' R
RIM = 549.29
INV (E) = 544.46
INV (W) = 544.19
TO BE ADJUSTED
NEW RIM EL = 549.30

PARKWAY DRIVE

MATCH LINE STA. 37+50.00
SEE ROADWAY PLAN AND PROFILE SHEET 3

EXISTING CURB INLET
STA 32+89.79 - 29.97' R
RIM = 548.06
INV = 546.04
TO BE REMOVED

PLUG EXISTING STORM SEWER

EXIST R.O.W.

EXISTING CURB INLET
STA 34+12.39 - 35.64' R
RIM = 548.25
INV (NE) = 546.27
INV (SW) = 546.00
TO BE RECONSTRUCTED

PLUG EXISTING STORM SEWER

PROP R.O.W.

P.C.C.

BIT.

N

0 10' 20' 40'
1" = 20'

PEKIN PARK DISTRICT

MATCH LINE STA 90+75.00
SEE ROADWAY PLAN AND PROFILE SHEET 5

HERGET NATIONAL BANK OF PEKIN

DTHC PROPERTIES

LEGEND
- SIDEWALK REMOVAL
- DRIVEWAY PAVEMENT REMOVAL
- MEDIAN REMOVAL
- HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT
- PAVEMENT REMOVAL
- COMBINATION CURB AND GUTTER REMOVAL

560 555 550 545 540 535 530

PROPOSED ROAD PROFILE

EXISTING ROAD PROFILE

-0.45% -0.11%

VPI STA 33+71.00
ELEVATION 548.47

32+00	32+50	33+00	33+50	34+00	34+50	35+00	35+50	36+00	36+50	37+00	37+50
548.71 / 549.24	548.52 / 549.12	548.39 / 549.01	548.26 / 548.90	548.20 / 548.79	548.22 / 548.68	548.27 / 548.56	548.29 / 548.47	548.19 / 548.44	548.18 / 548.41	548.27 / 548.38	548.31 / 548.35	548.30 / 548.32	548.37 / 548.30	548.32 / 548.27	548.10 / 548.24	548.01 / 548.21	547.90 / 548.18	547.82 / 548.15	547.76 / 548.12	547.69 / 548.10	547.62 / 548.07	547.51 / 548.04

MAURER-STUTZ, INC.

ROADWAY PLAN AND PROFILE SHEET 2

PARKWAY DRIVE STA. 32+00 TO 37+50