F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	142	19
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 95500

STORM SEWER SCHEDULE

LOCATION	TRENCH BACKFILL, SPECIAL	CLASS C PATCHES									STORM SEWER REMOVAL							REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	STORM SEWER CLASS A TYPE 1					STORM SEWER CLASS A TYPE 2								
		TYPE I 8 INCH	TYPE II 8 INCH	TYPE III 8 INCH	TYPE IV 8 INCH	TYPE II 10 INCH	TYPE III 10 INCH	TYPE IV 10 INCH	TYPE III 15 INCH	TYPE IV 15 INCH	6"	8"	10"	12"	15"	18"	24"				12"	24"	30"	36"	RUBBER GASKET 12"	12"	15"	18"	24"	30"	36"	42"	RUBBER GASKET 12"	24"
	CU. YD.	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
LT. STA. 609+84, 24.00'																																		
LT. STA. 609+84 TO LT. STA. 610+30																															40			
LT. STA. 610+30, 24.00'																																		
LT. STA. 610+30 TO LT. STA. 610+76	36.8																														40			
LT. STA. 610+76, 24.00'																																		
LT. STA. 610+76 TO LT. STA. 612+31	118.2			21.0	99.0																										156			
FIFTH STREET																																		
RT. STA. 502+51 TO RT. STA. 502+65	24.9														16												16							
LT. STA. 502+60, 29.17'																																		
LT. STA. 502+60 TO LT. STA. 502+75	2.1		8.0																						13									
RT. STA. 502+65, 27.12'		4.0																																
RT. STA. 502+65 TO RT. STA. 502+75	7.4																										8							
LT. STA. 502+75, 29.17'																																		
LT. STA. 502+75 TO RT. STA. 502+75	14.8			24.0																												48		
RT. STA. 502+75, 22.00'																																		
RT. STA. 502+75 TO RT. STA. 504+64.41	346.4				100.0					39.0				190															162					
RT. STA. 502+83.26																		1																
LT. STA. 503+75, 29.38'																																		
LT. STA. 503+75 TO LT. STA. 503+90	2.1																								13									
RT. STA. 503+81, 27.12'	2.1																									3								
LT. STA. 503+90, 29.38'																																		
LT. STA. 503+90 TO RT. STA. 503+90	16.4																															48		
RT. STA. 503+90, 22.00'																																		
RT. STA. 503+96, 27.12'	2.1																									3								
RT. STA. 504+13.08, 22.00'																																		
RT. STA. 504+64.41 TO RT. STA. 506+34	267.7				123.0								85	170																165				
RT. STA. 506+34, 22.00'	1.7																									5								
RT. STA. 506+34, 27.56'																																		
RT. STA. 506+34 TO RT. STA. 507+65	247.7				77.0								131	131																126				
LT. STA. 506+99 TO LT. STA. 507+68				23.0																														
RT. STA. 507+02, 27.63'	1.7																									5								
LT. STA. 507+02, 27.69'																																		
LT. STA. 507+02 TO LT. STA. 507+17	2.1																				13													
LT. STA. 507+17, 27.66'																			1															
LT. STA. 507+17 TO LT. STA. 507+50	21.3										33										31													
RT. STA. 507+17, 27.55'	1.7																		1							5								
RT. STA. 507+40, 27.42'	1.8																									5								
LT. STA. 507+50, 27.58'																																		
LT. STA. 507+50 TO LT. STA. 507+65	17.1										15			8							13													
LT. STA. 507+65, 27.55'																			1															
RT. STA. 507+65, 22.00'																																		
LT. STA. 507+65 TO RT. STA. 507+65	19.6																															46		
RT. STA. 507+65 TO RT. STA. 508+80	394.2				102.0									18			8	1																
RT. STA. 508+80, 22.00'																																		
RT. STA. 508+80 TO RT. STA. 509+41	92.1			21.0													61													56				
RT. STA. 509+41, 22.00'																																		
RT. STA. 509+41 TO RT. STA. 510+10	90.4				47.0												69													64				
RT. STA. 510+10, 22.00'																																		
RT. STA. 510+10 TO RT. STA. 512+07	211.7				68.0												197														192			
RT. STA. 512+07, 22.00'																																		
RT. STA. 512+07 TO RT. STA. 513+72	98.7			18.0																											160			
RT. STA. 513+72, 23.82'																																		
RT. STA. 513+72 TO RT. STA. 515+70	55.8																														196			
TOTAL	4720	12	13	123	974	6	19	861	43	209	104	80	326	597	112	211	399	5	23	2	503	356	47	159	160	324	252	741	409	411	655	308	398	32

FOR MORE ITEMS, SEE NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY KOJ

CHECKED BY BWC

H.M. & G. NO. 4812

CADD FILE: /4812/sch_4812.dgn
PLOTTED: 01/23/2007

HENRY, MEISENHEIMER & GENDE, INC. 1075 LAKE ROAD CARLYLE, ILLINOIS 62231 (618) 594-3711 WWW.HMGENGINEERS.COM