

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	062
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 98963				

### REMOVAL SCHEDULE - RAMPS

LOCATION STATION TO STATION	PAVED SHOULDER REMOVAL	PAVEMENT REMOVAL	PAVED DITCH REMOVAL	TREE REMOVAL	CONCRETE HEADWALL REMOVAL	REMOVING INLETS	CHAIN LINK FENCE REMOVAL
	SQ YD	SQ YD	FOOT	ACRE	EACH	EACH	FOOT
<b>I-57/I-64 NORTHBOUND</b>							
696+50 TO 711+65 (LT)	1346.7						
697+60.6 TO 706+76.3 (RT)	1221.0						
706+50.00 (RT) TO 733+92.62 (RT)							2743
706+64.5		233					
707+00 (0' RT)						1	
707+00 (108' RT)					1		
731+35 TO 759+15 (LT)	2471.1						
734+80.4 TO 756+01.7 (RT)	2828.4						
753+98.5 71.5' (RT) TO 756+01.1 83.0' (RT)		146					
755+00.5 100' (RT) TO 756+71 115.7' (RT)			171				
761+36.5 TO 765+55 (RT)	558.0						
<b>I-57/I-64 SOUTHBOUND</b>							
693+85 TO 713+30 (RT)	1728.9						
696+87.3 TO 709+97.5 (LT)	1746.9						
709+00.00 (LT) TO 737+00.00 (LT)							2800
717+54.63, 569.17' LT TO 722+89.43, 380.12' LT		1173					
729+35 TO 768+15 (RT)	3448.9						
732+33.8 TO 758+51.5 (LT)	3490.3						
748+81.9 106.6 (LT) TO 755+91.7 130.9 (LT)			711				
749+00 (93.6' LT)					1		
753+00.6 (71.0' LT) TO 756+51.5 (83.0' LT)		367					
<b>RAMP A</b>				3			
<b>RAMP B</b>				5			
<b>RAMP C</b>				1			
<b>RAMP D</b>				1			
<b>TOTALS</b>	<b>18840</b>	<b>1919</b>	<b>882</b>	<b>10</b>	<b>2</b>	<b>1</b>	<b>5543</b>

### STRUCTURE REMOVAL SCHEDULE - GRADE SEPARATION

LOCATION	REMOVING MANHOLES	REMOVING INLETS	HEADWALL REMOVAL
	EACH	EACH	EACH
<b>VETERANS MEMORIAL DRIVE</b>			
STA 62+52.68 25' RT.			
STA 49+57.53 55' LT.		1	
STA 62+54.13 14' LT.		1	
STA 65+66.32 14' LT. 5130		1	
STA 67+62.45 14' LT. 5133		1	
STA 68+63.59 14' LT. 5131		1	
STA 70+65.17 14' LT. 5136		1	
STA 72+65.38 14' LT.		1	
STA 48+43.71 61' LT.			1
STA 50+79.69 48' LT.			1
STA 62+00.77 37' LT.		1	
STA 69+65.42 14' LT.		1	
<b>SUBTOTAL</b>	<b>1</b>	<b>9</b>	<b>2</b>
<b>42ND STREET</b>			
STA 200+40.6 11' RT.	1		
STA 201+48.8 4' RT.	1		
STA 193+57.43 35' RT.		1	
STA 193+68.28 5' LT.		1	
STA 195+13.97 112' RT.		1	
STA 195+32.46 75' RT.		1	
STA 198+15.79 35' RT.		1	
STA 198+48.14 63, RT.		1	
STA 201+51.28 35' LT.		1	
STA 201+49.39 6' LT.		1	
STA 206+01.53 15' LT.		1	
STA 206+02.57 14' LT.		1	
STA 198+47.8 24' LT.			1
STA 200+43.2 22' RT.			1
STA 192+28.24 48' RT.		1	
STA 193+64.55 64' RT.		1	
<b>SUBTOTAL</b>	<b>2</b>	<b>10</b>	<b>2</b>
<b>SUBTOTAL</b>	<b>3</b>	<b>21</b>	<b>4</b>

### PAVEMENT REMOVAL SCHEDULE-GRADE SEPARATION

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL VAR. DEPTH	PAVEMENT REMOVAL
	SQ YD	SQ YD
<b>VETERANS MEMORIAL DRIVE</b>		
STA. 62+43.00 TO STA. 76+40.34		4157.8
<b>SUBTOTAL</b>		<b>4157.8</b>
<b>45TH STREET</b>		
STA 101+50.00 TO STA 102+31.16	189.2	
STA 102+31.16 TO STA 111+20.20		2322.7
<b>SUBTOTAL</b>	<b>189.2</b>	<b>2322.7</b>
<b>42ND STREET</b>		
STA. 192+15.21 TO STA. 199+56.00		2592.9
STA. 200+65.00 TO STA. 201+80.00		407.7
STA. 201+80.00 TO STA. 207+32.22		1608.1
<b>SUBTOTAL</b>		<b>4608.7</b>
<b>TEMPORARY ACCESS ROAD</b>		
STA. 11+00.00 TO STA. 17+40.38		1473.1
<b>SUBTOTAL</b>		<b>1473.1</b>
<b>SUBTOTAL</b>	<b>189.2</b>	<b>12562.3</b>
<b>USE TOTAL</b>	<b>189</b>	<b>12562</b>

### TREE REMOVAL SCHEDULE - GRADE SEPARATION

LOCATION	TREE REMOVAL 6-15 UNITS	TREE REMOVAL
	UNIT	ACRES
<b>VETERANS MEMORIAL DRIVE</b>		
RT. STA. 44+23.00 TO RT. STA. 45+43.00		0.32
RT. STA. 51+48.00 TO RT. STA. 53+00.00		0.31
RT. STA. 53+00.00 TO RT. STA. 54+96.00		0.42
RT. STA. 56+18.00 TO RT. STA. 198+00.00		1.88
LT. STA. 51+06.00 TO LT. STA. 53+00.00		0.40
LT. STA. 53+00.00 TO LT. STA. 60+81.00		2.02
LT. STA. 63+00.00 TO LT. STA. 65+00.00		0.17
LT. STA. 65+00.00 TO LT. STA. 72+43.00		0.37
RT. STA. 200+33.86	10	
LT. STA. 200+34.13	15	
LT. STA. 200+64.95	15	
LT. STA. 200+91.89	15	
LT. STA. 201+22.25	10	
<b>SUBTOTAL</b>	<b>65</b>	<b>5.89</b>
<b>42ND STREET</b>		
LT. STA. 194+23.00 TO LT. STA. 198+00.00		1.78
RT. STA. 200+74.00 TO RT. STA. 204+18.00		0.17
LT. STA. 202+96.00 TO LT. STA. 204+10.00		0.16
LT. STA. 202+64.96	15	
<b>SUBTOTAL</b>	<b>15</b>	<b>2.11</b>
<b>GRAND TOTAL</b>	<b>80</b>	<b>8.00</b>
<b>USE TOTAL</b>	<b>80</b>	<b>8</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
**VETERANS MEMORIAL DRIVE INTERCHANGE**  
**SECTION (41-3)HBK**  
SCALE: NO SCALE  
DATE 3-22-07  
DRAWN BY RL  
CHECKED BY MTM