

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	068
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 98963				

### THERMOPLASTIC PAVEMENT MARKING SCHEDULE - RAMPS

LOCATION STATION TO STATION	THERMOPLASTIC PAVEMENT MARKING LINE 4" (WHITE) FOOT	THERMOPLASTIC PAVEMENT MARKING LINE 4" (YELLOW) FOOT	THERMOPLASTIC PAVEMENT MARKING LINE 6" (WHITE) FOOT	THERMOPLASTIC PAVEMENT MARKING LINE 12" (WHITE) FOOT	THERMOPLASTIC PAVEMENT MARKING LINE 24" (WHITE) FOOT
<b>RAMP A</b> 300+33.9 RT 32.8 (STOP BAR) 300+99.3 LT 20.8' TO 315+56.3 LT 16' (SOLID) 301+19 RT 3.1' TO 322+77.0 RT 0' (SOLID)	2158.0	1457.0			15.0
<b>RAMP B</b> 400+00 RT 0' TO 420+67.4 RT 2.7' (SOLID) 406+59.6 LT 16' TO 421+07.9 LT 17.1' (SOLID) 421+03.7 RT 11.5' (STOP BAR) 421+10.9 RT 8.7' (STOP BAR) 421+26.2 (CROSS WALK) 421+33.5 (ISLAND)	2067.4	1448.3	115.8	65.9	18.0 18.0
<b>RAMP C</b> 500+35.3 RT 29.4' (STOP BAR) 500+61.7 (CROSS WALK) 500+99.7 LT 20.8' TO 515+51.1 LT 16' (SOLID) 501+19.0 RT 3.2' TO 528+08.8 RT 0' (SOLID)	2689.8	1451.4	115.7		18.0
<b>RAMP D</b> 600+00 RT 0' TO 616+74.0 RT 2.7' (SOLID) 604+54.8 LT 16' TO 617+13.1 LT 17.2' (SOLID) 617+29.2 RT 33.5' (STOP BAR) 617+33.4 RT 13.4' (STOP BAR) 617+39.1 (ISLAND)	1674.0	1258.3		65.9	18.0 18.0
<b>RAMP IL-15 NB</b> 756+01 TO 760+48 (SOLID) 756+88 TO 760+48 (SOLID)	447.0	360.0			
<b>RAMP IL-15 SB</b> 752+62.5 TO 762+15 (SOLID) 760+55 TO 762+48 (SOLID)	985.5	193.0			
<b>SUBTOTAL</b>	10021.7	6475.8	231.5	131.8	105.0
<b>TOTALS</b>		16,498	232	132	105

Copyright, Hansen Professional Services Inc. 2007  
**HANSON**  
 Hansen Professional Services Inc.

03/22/07 05:35 PM  
 I:\98\06s\98s20\98\road\stee\AC-610.scdan

LAYOUT	RET	02/26/04
DRAWN	JED	04/12/04
REVIEWED	MTM	03/22/07

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES  VETERANS MEMORIAL DRIVE INTERCHANGE SECTION (41-3)HBK  SCALE: NO SCALE DATE 3-22-07
DRAWN BY RLT		CHECKED BY MTM