F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	070
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 98963

PERMANENT PAVEMENT MARKING SCHEDULE - GRADE SEPARATION

					POLYUREA PM TYPE I 5"	POLYUREA PM TYPE I 6"	POLYUREA PM TYE I 12"	POLYUREA PM TYPE I 24"	POLYUREA PVT MK LTR-SYM	RAISED REFL PAVT MKR
					FOOT	FOOT	FOOT	FOOT	SQ FT	EACH
VETERANS MEMORIAL DRIVE										
STA.	34+75.84					102.0				
STA.	34+82.84					109.0				
STA.	35+65.00	TO	STA.	40+45.00		330.0				
STA.	35+65.00	TO	STA.	61+46.00	1127					63.0
STA.	35+65.00							65.0		
STA.	35+77.71								15.6	
STA.	36+06.58								20.8	
STA.	36+87.76								15.6	
STA.	37+16.56								20.8	
STA.	37+97.69								15.6	
STA.	38+26.54								20.8	
STA.	44+55.46	TO	STA.	48+58.24		253.0				
STA.	45+32.24							12.0		
STA.	51+21.64	TO	STA.	54+95.24		224.0				
STA.	54+17.64							12.0		
STA.	56+81.00	TO	STA.	61+46.00		315.0				
STA.	58+99.11								20.8	
STA.	59+27.94								15.6	
STA.	60+01.07								20.8	
STA.	61+03.10								20.8	
STA.	61+29.93								15.6	
STA.	61+31.95								15.6	
STA.	61+46.00							63.0		
STA.	62+42.00	TO	STA.	66+42.00		250.0				
STA.	62+42.00	TO	STA.	66+51.00	103.0					
STA.	62+42.00	TO	STA.	70+82.14	210.0					
STA.	62+42.00	TO	STA.	71+06.10						20.0
STA.	62+42.00							55.0		
STA.	62+55.89								15.6	
STA.	62+84.70								20.8	
STA.	63+25.51								15.6	
STA.	63+54.33								20.8	
STA.	63+95.06								15.6	
STA.	64+23.89								20.8	
STA.	67+15.00	TO	STA.	71+06.10	391.0					
STA.	71+06.10	TO	STA.	76+40.34	535.0					
				SUBTOTAL	2366.0	1583	0	207	328	83
45TH STREET										
STA.	101+60.00	TO	STA.	102+60.30	220.0					
STA.	101+60.00	TO	STA.	108+08.97	670.0					
STA.	101+60.00	TO	STA.	108+15.17	656.0					
STA.	101+60.00	TO	STA.	108+38.00						34.0
STA.	102+60.30	TO	STA.	107+18.00	1836.0		200.0			
STA.	107+18.00	TO	STA.	108+38.00	240.0	120.0				
STA.	107+18.00	TO	STA.	108+48.00						3.0
STA.	107+36.27								20.8	
STA.	107+57.03								15.6	
STA.	108+03.00								20.8	
STA.	108+23.83								15.6	
STA.	108+38.00							12.0		
STA.	108+48.00							32.0		
STA.	108+55.13					102.0				
STA.	108+65.38					109.0				
STA.	109+65.00	TO	STA.	110+95.00		120.0				
STA.	109+65.00							30.0		
STA.	109+75.00	TO	STA.	110+95.00	240.0					9.0
STA.	109+75.00							12.0		
STA.	109+88.87								15.6	
STA.	110+09.73								20.8	
STA.	110+56.12								15.6	
STA.	110+76.92								20.8	
STA.	110+95.00	TO	STA.	112+51.00	624.0		60.0			
				SUETOTAL	4486.0	451.0	280.0	86.0	145.6	46.0

PERMANENT PAVEMENT MARKING SCHEDULE - GRADE SEPARATION

					POLYUREA PM TYPE I 5"	POLYUREA PM TYPE I 6"	POLYUREA PM TYE I 12"	POLYUREA PM TYPE I 24"	POLYUREA PVT MK LTR-SYM	RAISED REFL PAVT MKR
					FOOT	FOOT	FOOT	FOOT	SQ FT	EACH
42ND STREET										
STA.	196+61.16	TO	STA.	198+24.25	668.0		71.0			
STA.	198+24.25	TO	STA.	199+35.00	222.0	111.0				9.0
STA.	198+42.36								20.8	
STA.	198+63.20								15.6	
STA.	199+01.11								20.8	
STA.	199+21.94								15.6	
STA.	199+35.00							36.0		
STA.	199+41.86					93.0				
STA.	199+51.98					116.0				
STA.	200+53.00	TO	STA.	202+33.00		180.0				
STA.	200+53.00							30.0		
STA.	200+63.00	TO	STA.	202+33.00	340.0					32.0
STA.	200+63.00	TO	STA.	207+32.15						4.0
STA.	200+63.00							12.0		
STA.	200+76.28								15.6	
STA.	201+05.12								20.8	
STA.	201+86.24								15.6	
STA.	202+15.08								20.8	
STA.	202+33.00	TO	STA.	206+67.00	1736.0		200.0			
STA.	206+67.00	TO	STA.	207+32.15	131.0					
				SUBTOTAL	3097.0	500.0	271.0	78.0	145.6	45.0
				TOTAL	9949.0	2534.0	531.0	371.0	618.8	174
				USE TOTAL	9949	2534	531	371	619	174

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

VETERANS MEMORIAL DRIVE
INTERCHANGE
SECTION (41-3)HBK

SCALE: NO SCALE — DRAWN BY RLT

DATE 3-22-07 — CHECKED BY MTM

©Copyright Hanson Professional Services Inc. 2007

HANSON
Hanson Professional Services Inc.

03/22/2007, 05:35 PM
f:\98 jobs\98s2019\roadway\steel\c-612-sch.dgn

LAYOUT	RLT	02/26/04
DRAWN	JCO	04/12/04
REVIEWED	MTM	05/22/07

12