

### SEEDING AND EROSION CONTROL SCHEDULE - RAMPS

LOCATION STATION TO STATION	SEEDING CLASS 2 (MODIFIED) ACRE	SEEDING CLASS 4 ACRE	SEEDING CLASS 7 ACRE	NITROGEN FERTILIZER NUTRIENT POUND	PHOSPHORUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND	AGRICULTURAL GROUND LIMESTONE TON	MULCH METHOD 2 ACRE	EROSION CONTROL BLANKET SQ YD	TEMPORARY EROSION CONTROL SEEDING POUND	STONE DUMPED RIPRAP, CLASS A4 SQ YD	PERIMETER EROSION BARRIER FOOT	INLET AND PIPE PROTECTION EACH
<b>I-57/I-64</b>													
691+75 (RT 13')													1
691+98 (LT 106')													1
703+00 TO 713+00 (MEDIAN)	1.8		1.8	288	216	216	3.6	3.6	355.6	540			
706+26 TO 721+55 RT	3.4		3.4	544	408	408	6.8	6.8	955.6	1020			
711+09 TO 722+59 LT		5.4	5.4	648	648	648	10.8	21.6		1620			
711+47 TO 723+24 LT	3.0		3.0	480	360	360	6	6.0	1111.1	900			
721+19 TO 735+17 RT	3.6		3.6	576	432	432	7.2	7.2	1211.1	1080			
722+96 TO 73644 LT	3.0		3.0	480	360	360	6	6.0		900			
723+69 TO 734+77 LT		3.1	3.1	124				6.2	1045.0	930			
742+12 TO 756+00 RT	2.3		2.3	368	276	276	4.6	4.6	622.2	690			
741+00 TO 75800 LT	2.5		2.5	400	300	300	5	5.0	755.6	750			
749+00 (LT 27')													1
<b>RAMP A</b>													
301+00 TO 322+50 RT	2.9		2.9	464	348	348	5.8	5.8	950.2	870			
301+50 (56') TO 306+50 (36') LT												480	
301+50 (45') TO 306+50 (21') RT												516	
<b>RAMP B</b>													
400+00 TO 420+50 RT	3.4		3.4	544	408	408	6.8	6.8	911.1	1020			
411+00 (LT 30')											48.83		1
414+50 (23') TO 420+50 (42') RT												601	
414+50 (40') TO 420+50 (57') LT												601	
<b>RAMP C</b>													
501+00 TO 528+00 RT	4.2		4.2	672	504	504	8.4	8.4	1200.0	1260			
503+50 (LT 84')											13.33		1
501+00 (56') TO 508+50 (39') LT												728	
501+00 (45') TO 508+50 (23') RT												770	
<b>RAMP D</b>													
600+00 TO 616+75 RT	2.6		2.6	416	312	312	5.2	5.2	755.6	780			
611+50 (57') TO 616+50 (37') LT												501	
612+00 (23') TO 616+50 (39.5') RT												451	
<b>VETERANS DRIVE</b>													
43+42 (LT 78')											13.85		1
<b>TOTALS</b>	32.7	8.5	41.2	6220	4572	4572	76.2	93.2	9873	12360	76.0	4648	6

Copyright Hanson Professional Services Inc. 2007  
**HANSON**  
 Hanson Professional Services Inc.

03/22/2007 05:35 PM  
 J:\98\jobs\98s20\road\sheet\ac-613-sch.dwg

LAYOUT	RLT	02/26/04
DRAWN	JEO	04/12/04
REVISION	MTV	03/22/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
**VETERANS MEMORIAL DRIVE INTERCHANGE**  
**SECTION (41-3)HBK**  
 SCALE: NO SCALE  
 DATE 3-22-07  
 DRAWN BY RLT  
 CHECKED BY MTM

Rev. 5-31-07