

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	081
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 98963				

# STORM SEWER SCHEDULES -- PIPES

PIPE/CULVERT NUMBER (P# / C#)	FROM STRUCTURE (S#)	INVERT ELEV. (FT)	TO STRUCTURE (S#)	INVERT ELEV. (FT)	PIPE SLOPE %	STORM SEWERS, CLASS A, TYPE 1					PIPE CULVERTS					PIPE CULVERTS CL A 24" (JACKED) (FT)	PIPE DRAINS 12" (FT)	CONCRETE COLLAR (CU YDS)	REINF. BARS (POUND)	PRE. CONC. BOX CULV. 4' X 2' (FT)	PRE. CONC. BOX CULV. 6' X 3' (FT)	TRENCH BACKFILL (CU YDS)	NOTES/REMARKS
						12" DIA. (FT)	15" DIA. (FT)	18" DIA. (FT)	24" DIA. (FT)	30" DIA. (FT)	36" DIA. (FT)	48" DIA. (FT)	48" DIA. (FT)	24" DIA. (FT)	36" DIA. (FT)								
<b>45TH STREET</b>																							
P61	S117	500.75	S118	500.50	0.15					16.6											0.4		
P62	S118	500.21	S119	500.10	0.11					93.4											11.6		
P63	S119	500.06	S120	500.03	0.11					24.2											2.1		
P64	S121	501.28	S118	501.21	0.22			31.9													3.3		
P65	S122	501.58	S121	501.30	0.26			106.4													11.2		
SUBTOTAL								138.3		134.2											28.6		
<b>RELOCATED GRAHAM ROAD</b>																							
P200	S143	503.25	S142	499.88	1.12					284.9													
SUBTOTAL										284.9													
<b>I-57/64</b>																							
P122	S86	501.54	S141	501.16	0.32															113.0			
P123	S141	501.16	S87	500.76	0.32															117.0			
SUBTOTAL																				230.0			
<b>ACCESS ROAD #1</b>																							
C11	S52	489.24	S53	489.17	0.12	22															53.0		
C12	S170	796.57	S171	496.38	0.86																14.9		
SUBTOTAL						22															53.0		
<b>ACCESS ROAD #2</b>																							
P127	S161	491.85	S162	490.50	1.00			70.0													4.3		
P128	S160	492.26	S161	492.02	3.21	24.0																	
P129	S165	493.31	S164	492.46	1.40	57.5																	
P130	S164	492.36	S161	492.26	4.00			2.5															
P131	S166	492.46	S160	492.36	4.00	2.5																	
SUBTOTAL						84.0		72.5													4.3		
GRAND TOTAL						853	69	424	378	134	115	253	166	183	480	230	1616	19.8	1848	4	53	595.4	

PIPE CULVERTS CLASS C, TYPE 1 12" (TEMPORARY) (FT)						
<b>TEMPORARY ACCESS ROAD</b>						
TP1	LT. END	496.20	RT. END	495.73	0.50	95
TP2	LT. END	497.12	RT. END	497.55	0.96	45
TOTAL						140

NOTE 1 - EXISTING PIPE TO REMAIN IN PLACE, CONTRACTOR SHALL CLEAN PIPE IF NECESSARY.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	DRAINAGE SCHEDULE	
		VETERANS MEMORIAL DRIVE INTERCHANGE SECTION (41-3)HBK	
		SCALE: NO SCALE DRAWN BY RLТ	
		DATE 3-22-07 CHECKED BY MTM	

