

F.A.I. RFE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	270
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SIGNS

LOCATION	SIGN PANEL - TYPE 3 SQ FT	CONCRETE FOUNDATION, GROUND MOUNT CU YD	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY POUND	CONCRETE FOUNDATIONS CU YD	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4' -0" X 4' -6") FOOT	OVERHEAD SIGN WALKWAY, TYPE A FOOT	REMOVE SIGN COMPLETE EACH	REMOVE CONCRETE FOUNDATION - GROUND MOUNT EACH	REMOVE SIGN PANEL EACH
INTERSTATE 57/64									
634B+00 RT - CAMPING/ATTRACTIONS (SIGN #1)	240	4.18	2125						
634B+00 RT - SECOND RIGHT (SIGN #2)	50								
642B+00 RT - LODGING (SIGN #3)	200	2.82	1394						
642B+00 RT - SECOND RIGHT (SIGN #2)	50								
650+00 RT - VETERANS MEM 1 MI (SIGN #4)	162.75	2.36	1017						
658+00 RT - LODGING (SIGN #5)	200	4.18	2193						
658+00 RT - SECOND RIGHT (SIGN #2)	50								
663+21 RT							1	2	
666+00 RT - FOOD (SIGN #6)	200	4.18	2178						
666+00 RT - SECOND RIGHT (SIGN #2)	50								
674+00 RT - VETERANS MEM 1/2 MI (SIGN #7)	162.75	2.36	1054				1	3	
681+90 RT							1	3	
682+00 RT - FOOD (SIGN # 8)	200	4.18	2254						
682+00 RT - SECOND RIGHT (SIGN #2)	50								
690+00 RT - GAS (SIGN #9)	150	2.36	986				1	3	
690+00 RT - SECOND RIGHT (SIGN #9A)	37.5								
698+00 RT							1	2	
700+50 RT - PROPOSED TRUSS				74	82	37.5			
VETERANS MEM (SIGN #10)	157.25 *								
ILL 15 3/4 MI (SIGN #11)	196 *								
716+00 RT - MT VERNON AIRPORT (#12)	80.5	1.4	564				1	2	
722+70 RT							1	2	
729+35 RT							1	2	
736+00 RT							1	2	
740+40 LT - PROPOSED TRUSS				74	91	48.5			
VETERANS MEM (SIGN #13)	157.25 *								
64/57 JUNCTION (SIGN #14)	300 *								
RAMP B STATION 322+00 RT - IL 15 1/4 MI (SIGN #15)	196	2.54	1378						
759+00 LT - VETERANS MEM 1/4 MI (SIGN #16)	162.75	2.36	1028						
STA 789+15 LT- EXISTING TRUSS									2
ILL 15 (SIGN #17)	198 *								
VETERANS MEM 3/4 MI (SIGN #18)	162.75 *								
VETERANS MEMORIAL DRIVE									
43+00 RT - (SIGN #19)	238	4.18	2175						
57N - 64W EFFINGHAM EAST ST LOUIS									
57S - 64E CAIRO EVANSVILLE									
45+35 LT - (SIGN #20)	119	3.8	2094						
57N - 64E CAIRO EVANSVILLE									
47+70 RT - (SIGN #21)	72	1.4	735						
57N - 64W DOUBLE ARROWS									
51+50 LT - (SIGN #22)	72	3.6	1215						
57S - 64E COUBLE ARROWS									
54+00 RT - (SIGN #23)	119	3.6	1239						
57N - 64W EFFINGHAM EAST ST LOUIS									
56+30 LT - (SIGN #24)	238	4.46	3182						
57S - 64E CAIRO EVANSVILLE									
57N - 64W EFFINGHAM EAST ST LOUIS									
TOTALS	4272	54	26811	148	173	86	9	21	2

* PROPOSED SIGN PANELS PLACED ON TRUSSES (1171.25 SQ FT) WILL BE PAID FOR AS 100% STATE. A FLEXIBLE COLORED SUPER-HIGH EFFICIENCY FULL CUBE RETROFLECTIVE SHEETING WILL BE APPLIED TO THESE PANELS, SEE SPECIAL PROVISIONS FOR DETAILS.

PLOT DATE = 03/21/2007, 09:05 AM
 FILE NAME = I:\98\98963\98963\98963\DOT\98963\98963\98963.dwg
 PLOT SCALE = 50.0000 / IN.
 USER NAME = kcs

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SIGN SCHEDULE

SCALE: VERT. NONE
 DATE: HORIZ. NONE
 DRAWN BY: CHECKED BY:

SIGN SCHEDULE