

TR-004

DATE	REVISION	BY

SUMMARY OF QUANTITIES

ITEM No.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS-BUILT QUANTITIES
AR201660	BITUMINOUS CRACK REPAIR	LF.	1,311	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	6,364	
AR401655	BUTT JOINT CONSTRUCTION	S.Y.	95	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	144	
AR402622	POROUS FRICTION COURSE, 0.10'	S.Y.	7,685	
AR603510	BITUMINOUS TACK COAT	GAL.	2,306	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	526	


INDEX TO SHEETS

SHEET No.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED CONSTRUCTION PLAN
5	PROPOSED PAVEMENT PREPARATION PLAN
6	PROPOSED STAKING PLAN
7	PROPOSED MARKING PLAN
8	PROPOSED CROSS-SECTIONS FOR HANGAR PAVEMENT STA. 10+34.80 TO STA. 10+50
9	PROPOSED CROSS-SECTIONS FOR HANGAR PAVEMENT STA. 10+75 TO STA. 11+00
10	PROPOSED CROSS-SECTIONS FOR HANGAR PAVEMENT STA. 11+25 TO STA. 11+50
11	PROPOSED CROSS-SECTIONS FOR HANGAR PAVEMENT STA. 11+75 TO STA. 12+00
12	PROPOSED CROSS-SECTIONS FOR HANGAR PAVEMENT STA. 12+25 TO STA. 12+50
13	PROPOSED CROSS-SECTIONS FOR HANGAR PAVEMENT STA. 12+75 TO STA. 13+00
14	PROPOSED CROSS-SECTIONS FOR HANGAR PAVEMENT STA. 13+25 TO STA. 13+50
15	PROPOSED CROSS-SECTIONS FOR HANGAR PAVEMENT STA. 13+75 TO STA. 14+00
16	PROPOSED CROSS-SECTIONS FOR HANGAR PAVEMENT STA. 14+25 TO STA. 14+50
17	PROPOSED CROSS-SECTIONS FOR HANGAR PAVEMENT STA. 14+75

TRI-TOWNSHIP AIRPORT
SAVANNA, CARROLL COUNTY
ILLINOIS

IL PROJ.: SFT-3712 A.I.P. PROJ.: 3-17-0091-B13

Hanson Project No.	82607IXYD_0800
Filename	R-002FLP.DWG
Scale	NOT TO SCALE
Date	04/02/07
LAYOUT	CCC 04/02/07
DRAWN	CCC 04/02/07
REVIEWED	CAH 06/12/07



OVERLAY HANGAR
APRON AND TAXIWAY
SUMMARY OF QUANTITIES
AND
INDEX TO SHEETS