	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE											
					80% FED. 20% STATE	80% STATE 20% MONT-GOMERY	80% STATE 20% OSWEGO	80% FED. 20% STATE	80% FED. 10% STATE 5% MONT-GOMERY 5% OSWEGO TOWNSHIP	80% FED. 10% STATE 5% OSWEGO 5% MONT-GOMERY	80% FED. 10% STATE 5% OSWEGO 5% MONT-GOMERY	100% MONT-GOMERY	50% OSWEGO 50% MONT-GOMERY	80% FED. 20% STATE	80% FED. 20% STATE	100% OSWEGO
								BRIDGE REPLACEMENT S.N.					STREET LIGHTING	NOISE ABATEMENT WALLS	WATER MAIN	
					ROADWAY	SIDEWALK	SIDEWALK	047-0301	BRIARCLIFF	DOUGLAS	FIFTH	GOODWIN DR.				
					0003	0021	0021	0010	TRAFFIC SIGNALS - 0021				0021	0040	0043	0043
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
+	25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	9,905	9,905											
+	25200110	SODDING, SALT TOLERANT	SQ YD	17,850	17,850											
+	25200200	SUPPLEMENTAL WATERING	UNIT	40	40											
	28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	360	360											
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10,139	10,139											
	28000305	TEMPORARY DITCH CHECKS	FOOT	1,468	1,468											
	28000400	PERIMETER EROSION BARRIER	FOOT	10,934	10,884										50	
	28000500	INLET AND PIPE PROTECTION	EACH	20	20											
	28000510	INLET FILTERS	EACH	280	280											
	28001000	AGGREGATE (EROSION CONTROL)	TON	681	681											
	28100105	STONE RIPRAP, CLASS A3	SQ YD	32	32											
	28100107	STONE RIPRAP, CLASS A4	SQ YD	22	22											
	28100109	STONE RIPRAP, CLASS A5	SQ YD	1,698	68			1,630								
	28200200	FILTER FABRIC	SQ YD	2,698	1,068			1,630								

+ SPECIALTY ITEM • 100% OSWEGO

FILE NAME = S:\JOL\6288-6399\6316\823\Mcros\Sht\0158132-sht-sos.dgn

STRAND ASSOCIATES, INC. ENGINEERS
1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = amanday	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 20.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 5/14/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: AS SHOWN | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	II WRS-3	KENDALL	527	7
		CONTRACT NO. 60132		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT