	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE											
					80% FED. 20% STATE	80% STATE 20% MONT-GOMERY	80% STATE 20% OSWEGO	80% FED. 20% STATE	80% FED. 10% STATE 5% MONT-GOMERY 5% OSWEGO TOWNSHIP	80% FED. 10% STATE 5% OSWEGO 5% MONT-GOMERY	80% FED. 10% STATE 5% OSWEGO 5% MONT-GOMERY	100% MONT-GOMERY	50% OSWEGO 50% MONT-GOMERY	80% FED. 20% STATE	80% FED. 20% STATE	100% OSWEGO
								BRIDGE REPLACEMENT S.N. 047-0301					STREET LIGHTING	NOISE ABATEMENT WALLS	WATER MAIN	
					ROADWAY	SIDEWALK	SIDEWALK		BRIARCLIFF	DOUGLAS	FIFTH	GOODWIN DR.				
					0003	0021	0021	0010	TRAFFIC SIGNALS - 0021				0021	0040	0043	0043
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
+	81400300	DOUBLE HANDHOLE	EACH	4						2	2					
+	81603050	UNIT DUCT, 600V, 3-1C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2,563									2,563			
+	81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	185									185			
+	81800330	AERIAL CABLE, 3-1/C NO. 6 WITH MESSENGER WIRE	FOOT	597									597			
+	82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	14									14			
+	82500335	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 100AMP	EACH	2									2			
+	83050805	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 12 FT. DAVIT ARM	EACH	12									12			
+	83050825	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. DAVIT ARM	EACH	2									2			
+	83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	2									2			
+	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	84									84			
+	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	11									11			
+	83800505	BREAKAWAY DEVICE, COUPLING WITH ALUMINUM SKIRT	EACH	8									8			
+	84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	2									2			
+	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1									1			

+ SPECIALTY ITEM • 100% OSWEGO

FILE NAME = S:\DL16303-6399\6346\8231\Micro\Sht\01\60132-sht-sosu.dgn

STRAND ASSOCIATES, INC. ENGINEERS
1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = amendej	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 20.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 5/14/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: AS SHOWN | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	11 WRS-3	KENDALL	527	22
		CONTRACT NO. 60132		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		