

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE												
				80% FED. 20% STATE	80% STATE 20% MONT-GOMERY	80% STATE 20% OSWEGO	80% FED. 20% STATE	80% FED. 10% STATE 5% MONT-GOMERY 5% OSWEGO TOWNSHIP	80% FED. 10% STATE 5% OSWEGO 5% MONT-GOMERY	80% FED. 10% STATE 5% OSWEGO 5% MONT-GOMERY	100% MONT-GOMERY	50% OSWEGO 50% MONT-GOMERY	80% FED. 20% STATE	80% FED. 20% STATE	100% OSWEGO	
				ROADWAY	SIDEWALK	SIDEWALK	BRIDGE REPLACEMENT S. N. 047-0301	BRIARCLIFF	DOUGLAS	FIFTH	GOODWIN DR.	STREET LIGHTING	NOISE ABATEMENT WALLS	WATER MAIN		
				0003	0021	0021	0010	TRAFFIC SIGNALS - 0021			0021	0040	0043	0043		
URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN				
Δ X5538200	STORM SEWERS TO BE CLEANED 24"	FOOT	829	829												
X5610712	WATER MAIN REMOVAL, 12"	FOOT	225												225	
X5610716	WATER MAIN REMOVAL, 16"	FOOT	665												665	
X6020096	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	8	8												
X6024240	INLETS, SPECIAL	EACH	1	1												
X6025600	MANHOLES TO BE ADJUSTED (SPECIAL)	EACH	6	6												
X6026622	VALVE VAULTS TO BE REMOVED	EACH	2												2	
X6061900	CONCRETE MEDIAN, TYPE SB-6.12 (SPECIAL)	SO FT	3,349	3,349												
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	24	24												
X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	24	24												
+ X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1												
+ X7010240	TRAFFIC CONTROL SURVEILLANCE (SPECIAL)	CAL DA	687	687												
X7240500	RELOCATE EXISTING SIGNS	EACH	1	1												
+ X8100105	CONDUIT SPLICE	EACH	1							**	1					

FILE NAME: S:\JUL\6388-8394\6346\023\Access\Shet.D160132-shr-soq.dgn

+ SPECIALTY ITEM • 100% OSWEGO Δ 100% STATE ** 80% FED./20% STATE



1170 SOUTH HOUBOLT ROAD JOLIET, ILLINOIS 60431 (815) 744-4200	USER NAME: amanda	DESIGNED -	REVISED -
PLOT SCALE: 1/8" = 1' / in.	PLOT DATE: 5/14/2012	DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE: AS SHOWN	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.P. RTE. 349	SECTION 11 WRS-3	COUNTY KENDALL	TOTAL SHEETS 527	SHEET NO. 29
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Rev.

CONTRACT NO. 60132