

SCHEDULE OF TREE REMOVAL			
STATION	OFFSET	TREE REMOVAL (6 TO 15 UNITS DIAMETER) (UNIT) 20100110	TREE REMOVAL (OVER 15 UNITS DIAMETER) (UNIT) 20100210
US ROUTE 30			
312+82.24	55.74 LT	12	
318+26.01	57.00 LT	8	
318+26.01	57.00 LT	8	
319+75.02	56.9 LT	8	
319+75.02	56.9 LT	8	
320+07.60	54.23 LT	6	
320+07.60	54.23 LT	6	
320+07.60	54.23 LT	6	
320+07.60	54.23 LT	6	
320+93.34	53.99 LT	12	
321+14.16	57.73 LT	12	
321+65.04	56.12 LT	15	
321+89.13	58.39 LT	8	
321+89.13	58.39 LT	8	
324+97.47	59.33 LT	6	
329+01.96	69.46 RT		18
329+04.49	81.25 RT	6	
329+06.10	75.89 RT	6	
338+27.69	60.74 LT	6	
344+12.45	69.38 RT		30
345+23.09	58.47 LT	12	
345+23.10	58.48 RT	12	
363+41.08	59.96 RT	12	
363+41.08	59.96 RT	12	
363+41.08	59.96 RT	12	
363+41.08	59.96 RT	12	
363+41.08	59.96 RT	12	
363+41.08	59.96 RT	12	
363+41.08	59.96 RT	12	
363+41.08	59.96 RT	12	
373+35.50	60.73 RT	12	
373+35.50	60.73 RT	12	
395+65.56	35.42 LT		24
395+65.70	35.83 LT	12	
395+71.09	38.23 LT		16
395+71.09	38.23 LT		16
395+71.09	38.23 LT		16
395+74.71	43.59 LT		18
395+75.61	41.69 LT	12	
395+75.61	41.69 LT	12	
395+75.61	41.69 LT	12	
396+67.45	39.58 LT		30
397+20.88	40.95 LT		30
397+20.91	33.08 LT		18
397+55.04	36.5 LT	12	
397+55.04	36.5 LT	12	
397+55.04	36.5 LT	12	
397+96.91	36.5 LT		18
397+96.91	36.5 LT		18
397+96.91	36.5 LT		18
398+22.96	36.46 LT	12	
398+22.96	36.46 LT	12	
398+26.44	30.85 LT		18
398+26.44	30.85 LT		18
418+92.00	35.3 RT	12	
418+97.68	35.23 RT	8	
419+75.62	37.66 RT	6	
419+76.50	42.32 RT	6	
420+05.90	89.80 LT	8	
	SUBTOTAL	439	306

SCHEDULE OF TREE REMOVAL			
STATION	OFFSET	TREE REMOVAL (6 TO 15 UNITS DIAMETER) (UNIT) 20100110	TREE REMOVAL (OVER 15 UNITS DIAMETER) (UNIT) 20100210
420+05.90	89.80 LT	8	
420+71.86	30.36 LT	12	
420+71.86	30.36 LT	12	
420+91.41	81.91 LT	8	
420+91.41	81.91 LT	8	
420+96.76	71.18 LT	12	
420+97.60	51.02 LT	12	
421+07.92	46.66 LT	12	
421+17.64	53.48 LT		30
421+40.73	47.22 LT		18
421+40.73	47.22 LT		18
421+42.43	106.17 LT	12	
421+42.43	106.17 LT	12	
421+42.43	106.17 LT	12	
421+42.43	106.17 LT	12	
421+44.18	100.02 LT	12	
421+44.81	95.85 LT	12	
DOUGLAS RD.			
208+85.96	46.83 RT		15
209+27.44	52.16 RT	12	
209+65.88	46.77 RT	6	
209+65.88	46.77 RT	6	
209+65.88	46.77 RT	6	
209+65.88	46.77 RT	8	
209+65.88	46.77 RT	10	
213+16.90	43.98 RT	10	
213+44.08	39.61 RT	10	
	SUBTOTAL	224	81
	TOTAL	663	387

SCHEDULE OF POROUS GRANULAR EMBANKMENT		
STATION	REMARKS	(CU YD) 20700200
US ROUTE 30		
398+65	EXISTING CATTLE PASS	180
	TOTAL	180

MAINLINE US RTE. 30 PRE-STAGE EARTHWORK COMPUTATION									
LOCATION		EARTH EXCAVATION 20200100	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)	EMBANKMENT	FURNISHED EXCAVATION 20400800	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT (4")	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL 20201200	
STATION	STATION	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-)	UNDERCUT AND OTHER UNSUITABLE MATERIAL
306+00	307+00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
307+00	308+00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
308+00	309+00	1.46	1.24	0.00	1.24	0.00	0.00	0.00	0.00
309+00	310+00	4.18	3.55	0.00	3.55	0.00	0.00	0.00	0.00
310+00	311+00	4.74	4.03	0.00	4.03	0.00	0.00	0.00	0.00
311+00	312+00	4.13	3.51	0.00	3.51	0.00	0.00	0.00	0.00
312+00	313+00	4.77	4.06	0.00	4.06	0.00	0.17	-0.17	0.00
313+00	314+00	5.56	4.73	0.00	4.73	0.00	0.68	-0.68	0.00
314+00	315+00	6.67	5.67	0.35	5.32	0.00	1.48	-1.48	0.00
315+00	316+00	7.54	6.41	1.17	5.24	0.00	2.52	-2.52	0.00
316+00	317+00	7.21	6.13	3.55	2.58	3.00	3.67	-0.68	0.00
317+00	318+00	11.30	9.61	3.96	5.64	7.10	3.41	3.68	0.00
318+00	319+00	16.87	14.34	2.27	12.06	9.40	2.38	7.02	0.00
319+00	320+00	17.94	15.25	3.87	11.37	18.86	3.35	15.51	0.00
320+00	321+00	16.17	13.74	10.98	2.76	33.79	5.88	27.91	0.00
321+00	322+00	15.67	13.32	46.02	-32.70	50.69	10.89	39.80	0.00
322+00	323+00	29.84	25.36	87.23	-61.87	60.64	14.71	45.93	0.00
323+00	324+00	40.21	34.17	98.34	-64.16	57.62	14.09	43.53	0.00
324+00	325+00	35.19	29.91	97.36	-67.45	54.22	13.10	41.12	0.00
325+00	326+00	34.44	29.28	98.10	-68.82	54.26	13.26	41.01	0.00
326+00	327+00	35.16	29.89	107.41	-77.52	58.59	14.82	43.78	0.00
327+00	328+00	35.65	30.30	121.35	-91.05	63.94	16.56	47.38	0.00
328+00	329+00	35.19	29.91	128.71	-98.79	67.79	17.60	50.19	0.00
329+00	330+00	46.98	39.93	135.59	-95.66	76.56	23.21	53.35	0.00
330+00	331+00	51.01	43.36	104.58	-61.23	91.05	27.17	63.89	0.00
331+00	332+00	39.49	33.56	111.94	-78.38	83.00	23.59	59.41	0.00
332+00	333+00	17.08	14.51	124.75	-110.24	81.55	22.84	58.71	30.23
333+00	334+00	0.00	0.00	100.31	-100.31	80.11	22.32	57.79	63.33
334+00	335+00	0.00	0.00	80.46	-80.46	73.27	19.57	53.70	65.28
335+00	336+00	0.00	0.00	81.97	-81.97	71.14	18.81	52.33	63.39
336+00	337+00	0.00	0.00	67.80	-67.80	73.90	20.20	53.70	68.11
337+00	338+00	0.00	0.00	61.16	-61.16	71.69	19.09	52.60	69.78
338+00	339+00	22.56	19.17	74.47	-55.29	69.80	17.95	51.85	32.88
339+00	340+00	40.97	34.82	103.61	-68.78	76.23	20.77	55.46	0.00
340+00	341+00	34.67	29.47	143.04	-113.58	86.32	25.12	61.19	0.00
341+00	342+00	34.53	29.35	185.67	-156.32	93.92	28.01	65.91	0.00
342+00	343+00	34.40	29.24	251.55	-222.31	101.91	29.98	71.93	0.00
343+00	344+00	31.72	26.96	384.96	-358.00	117.25	34.78	82.48	0.00
344+00	345+00	135.35	115.05	339.56	-224.51	136.47	45.69	90.78	0.00
345+00	346+00	33.52	28.49	287.70	-259.21	99.54	31.33	68.21	0.00
346+00	347+00	38.00	32.30	220.28	-187.99	96.04	30.73	65.31	0.00
347+00	348+00	40.71	34.60	146.08	-111.47	90.74	30.14	60.60	0.00
348+00	349+00	40.30	34.25	92.31	-58.06	78.71	27.81	50.90	0.00
349+00	350+00	37.83	32.15	40.43	-8.28	41.63	15.82	25.81	0.00
350+00	351+00	17.24	14.65	9.83	4.82	11.45	6.23	5.21	27.56
351+00	352+00	0.00	0.00	5.26	-5.26	3.71	4.19	-0.48	52.91
352+00	353+00	0.00	0.00	7.41	-7.41	7.90	5.16	2.74	54.81
353+00	354+00	14.72	12.51	40.98	-28.47	31.56	12.20	19.36	29.46
354+00	355+00	29.43	25.02	79.45	-54.43	49.00	15.14	33.86	0.00
355+00	356+00	33.02	28.07	66.94	-38.87	57.46	13.87	43.59	0.00
356+00	357+00	71.37	60.67	23.88	36.78	76.05	17.88	58.17	0.00
357+00	358+00	86.64	73.65	8.96	64.69	81.44	20.46	60.98	0.00
358+00	359+00	36.13	30.71	3.04	27.67	38.33	9.35	28.98	0.00
359+00	360+00	20.36	17.31	32.47	-15.16	46.16	3.10	43.06	0.00
360+00	361+00	38.05	32.34	81.41	-49.07	73.48	8.68	64.80	0.00
361+00	362+00	36.53	31.05	77.07	-46.02	53.29	10.63	42.66	0.00
362+00	363+00	36.51	31.04	62.40	-31.36	50.47	11.35	39.12	0.00
363+00	364+00	32.94	28.00	68.19	-40.19	48.11	13.88	34.23	0.00
364+00	365+00	31.31	26.61	56.19	-29.58	42.69	15.01	27.69	0.00
	SUBTOTAL	1533.25	1303.26	4572.36	-3269.10	3001.84	840.66	2161.18	557.74

FILE NAME = s:\p1\6300--6395\6346\023\micro\sh1\018132-sh1-schedule.dgn



1170 SOUTH HOUBOLT ROAD  
JOLIET, ILLINOIS 60431  
(815) 744-4200

USER NAME = amandaj  
DESIGNED -  
DRAWN -  
PLOT SCALE = 48.0000' / in.  
PLOT DATE = 5/14/2012

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES  
SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.  
349 11 WRS-3 KENDALL 527 43  
CONTRACT NO. 60132  
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT