

SCHEDULE OF SIGNING ITEMS

STATION	OFFSET	DESCRIPTION	SIGN PANEL - TYPE 1 (SQ FT) 72000100	SIGN PANEL - TYPE 2 (SQ FT) 72000200	REMOVE SIGN PANEL ASSEMBLY - TYPE A (EACH) 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE B (EACH) 72400200	OBJECT MARKER - TYPE 3 (EACH) 72500300	TELESCOPING STEEL SIGN SUPPORT (FOOT) 72800100	BASE FOR TELESCOPING STEEL SIGN SUPPORT (EACH) 73100100	RELOCATE EXISTING SIGNS (EACH) X7240500
307+50	RT	M3-2	2.00				24.5			
307+50	RT	M1-4/US 30	4.00							
307+50	N/A	M3-2			1					
311+00	RT	SPEED/LIMIT/45		12			20.0			
311+00	LT	SPEED/LIMIT/45		12			18.5			
311+00	N/A	SPEED/LIMIT/45			1					
311+00	N/A	SPEED/LIMIT/45			1					
313+25	N/A	W4-2R			1					
318+75	LT	W16-8P/BRIARCLIFF ROAD	2.68				20.0			
318+75	LT	W3-3	9.00							
318+75	N/A	W3-3			1					
322+53	N/A	W6-1			1					
328+00	RT	SPEED/LIMIT/45		12			20.5			
328+00	LT	SPEED/LIMIT/45		12			21.5			
328+00	N/A	SPEED/LIMIT/45			1					
328+00	N/A	SPEED/LIMIT/45			1					
341+00	RT	SPEED/LIMIT/45		12			21.5			
341+00	LT	SPEED/LIMIT/45		12			20.5			
341+00	N/A	SPEED/LIMIT/45		12			20.5			
341+00	N/A	SPEED/LIMIT/45			1					
341+00	N/A	SPEED/LIMIT/45			1					
349+00	N/A	NO/PARKING/ANY/TIME			1					
351+75	N/A	NO/PARKING/ANY/TIME			1					
353+00	LT	SPEED/LIMIT/45		12			21.0			
353+00	N/A	SPEED/LIMIT/45			1					
353+10	N/A	NO/PARKING/ANY/TIME			1					
353+65	RT	LT ONLY/LT ONLY	6.25				12.5			
354+67	N/A	W4-2R			1					
355+92	N/A	NO/PARKING/ANY/TIME			1					
356+80	LT	M3-4	2.00				12.5			
356+80	LT	M1-4/US 30	4.00							
356+80	N/A	NO/PARKING/ALONG/HIGHWAY			1					
357+56	N/A	W4-2R			1					
358+00	N/A	NO/PARKING/ANY/TIME			1					
358+49	RT	LT ONLY/LT ONLY	6.25				12.5	1		
358+49	RT	R4-7	5.00							
358+70	RT	LEFT ON/GREEN/ARROW/ONLY	7.50							
359+90	LT	LEFT ON/GREEN/ARROW/ONLY	7.50							
360+06	RT	LT ONLY/LT ONLY	6.25				12.5	1		
360+06	RT	R4-7	5.00							
361+50	RT	M3-2	2.00				15.0			
361+50	RT	M1-4/US 30	4.00							
364+00	RT	LT ONLY/LT ONLY	6.25				12.5			
364+00	RT	SPEED/LIMIT/45		12			16.0			
365+00	N/A	NO/PARKING/ANY/TIME			1					
366+00	RT	W11-8	9.00				18.0			
366+00	N/A	W11-8			1					
370+89	LT	SPEED/LIMIT/45		12			21.0			
372+00	LT	M3-4	2.00				18.0			
372+00	LT	M1-4/US 30	4.00							
373+12	N/A	R3-5R			1					
373+42	LT	R3-5L	5.00				13.0	1		
373+42	LT	R4-7	5.00							
374+65	RT	R3-5L	5.00				13.0	1		
374+65	RT	R4-7	5.00							
375+33	N/A	NO/PARKING			1					
376+00	RT	M3-2	2.00				15.0			
376+00	RT	M1-4/US 30	4.00							
SUBTOTAL			120.68	132.00	23.00	0.00	0.00	400.00	4.00	0.00

SCHEDULE OF SIGNING ITEMS

STATION	OFFSET	DESCRIPTION	SIGN PANEL - TYPE 1 (SQ FT) 72000100	SIGN PANEL - TYPE 2 (SQ FT) 72000200	REMOVE SIGN PANEL ASSEMBLY - TYPE A (EACH) 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE B (EACH) 72400200	OBJECT MARKER - TYPE 3 (EACH) 72500300	TELESCOPING STEEL SIGN SUPPORT (FOOT) 72800100	BASE FOR TELESCOPING STEEL SIGN SUPPORT (EACH) 73100100	RELOCATE EXISTING SIGNS (EACH) X7240500
377+50	RT	SPEED/LIMIT/45		12			21.0			
380+00	LT	W11-8	6.25				15.5			
380+00	N/A	W11-8			1					
384+00	N/A	SPEED/LIMIT/45			1					
384+00	N/A	SPEED/LIMIT/45			1					
397+00	LT	SPEED/LIMIT/45		12			21.0			
397+00	RT	SPEED/LIMIT/45		12			21.0			
397+00	N/A	SPEED/LIMIT/45		12			21.0			
397+00	N/A	SPEED/LIMIT/45		12						
414+00	LT	SPEED/LIMIT/45		12			21.0			
414+00	RT	SPEED/LIMIT/45		12			21.0			
418+00	LT	Route 31 4 - Rock Falls	77	17			35.0			
420+07	LT	OM3-L					15	1		
420+07	RT	OM3-R					15	1		
420+14	LT	OM3-L					15	1		
420+14	RT	OM3-R					15	1		
422+68	N/A	W6-1			1					
423+40	N/A	W6-1			1					
427+50	N/A	LT ONLY/LT ONLY/THRU				1				
431+00	LT	LT ONLY/LT ONLY	6.25				12.5		1	
431+00	N/A	LT ONLY/LT ONLY			1					
431+50	LT	SPEED/LIMIT/45		12			21.0			
431+55	N/A	W4-2R			1					
433+10	LT	M3-4	2.00				12.5			
433+10	LT	M1-4/US 30	4.00							
433+77	LT	LT ONLY/LT ONLY	6.25				12.5		1	
433+77	LT	R4-7	5.00							
433+77	N/A	LT ONLY/LT ONLY			1					
434+62	RT	W1-7	8.00				28.0			
434+62	N/A	W1-7				1				
435+08	RT	R4-7	5.00				14.5			
435+08	N/A	R4-7			1					
435+50	LT	R3-5R	5.00				15.0			
435+50	N/A	R3-5R			1					
436+00	RT	M2-1	3.13				15.5			
436+00	RT	M1-4/US 34	4.00							
436+00	N/A	M2-1			1					
436+50	RT	R3-7L	6.25				14.5			
436+50	RT	R3-7L	6.25				14.5			
436+50	N/A	R3-7L			1					
436+50	N/A	R3-7L			1					
436+90	LT	R3-5R	5.00				15.0			
437+00	N/A	R3-5R			1					
437+95	LT	SPEED/LIMIT/45		12			15.0			
438+00	N/A	SPEED/LIMIT/45			1					
DOUGLAS RD.										
206+57	RT	R4-7	5.00				14.5			
206+57	N/A	R4-7			1					
209+70	LT	R3-5L	5.00				13.0		1	
209+70	LT	R4-7	5.00							
211+60	RT	EXISTING WELCOME SIGN								1
212+26	LT	END/CLASS II/TRUCK/ROUTE		12			18.0			
212+26	N/A	END/CLASS II/TRUCK/ROUTE			1					
MAST ARM SIGNS			113							
SUBTOTAL			200	125	17	2	4	452	3	1
TOTAL			321.25	132	23	2	4	400	4	0

FILE NAME = s:\j\p1\6380--6395\6346\023\micro\sh1\018132-sh1-schedule.dgn



USER NAME = amandaj
 PLOT SCALE = 48.0000' / in.
 PLOT DATE = 5/14/2012

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	11 WRS-3	KENDALL	527	61
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60132	