

TEMPORARY DRAINAGE NOTES:

1. REFER TO THE EXISTING DRAINAGE STRUCTURE SCHEDULE FOR TEMPORARY FRAME, GRATE, LID, AND STRUCTURE ADJUSTMENTS.
2. TEMPORARY DITCH PROFILES ARE SHOWN IN THE TEMPORARY DITCH PROFILE SHEETS.
3. TEMPORARY DRAINAGE FACILITIES (CULVERTS, END SECTIONS, STORM SEWER, AND STRUCTURES) ARE SHOWN IN THE MAINTENANCE OF TRAFFIC SHEETS.
4. SEE PRE-STAGE US ROUTE 30 AND DOUGLAS ROAD FOR TEMPORARY STORM SEWER AND INLETS, SPECIAL.
5. PIPE CULVERTS BEING EXTENDED SHALL BE CLEANED PRIOR TO EXTENSION.

TEMPORARY CULVERT EXTENSION AND END SECTION SCHEDULE										
STATION	EXISTING CULVERT END OFFSET	LENGTH (FT) OF EXTENSION	DIA (IN)	PIPE TYPE	SLOPE (%)	FLOW	END SECTION TYPE	END SECTION STATION	END SECTION OFFSET	CONSTRUCTION STAGE
352+10	43 LT	7	18	PIPE CULVERTS, CLASS A, TYPE 1 18" (TEMPORARY)	0.50%	NORTH	ENDS SECTIONS 18"	352+10	50 RT	STAGE I
373+23	47 RT	32	14x23	PIPE CULVERTS, CLASS A, TYPE 1 18" EQUIVALENT	1.60%	EAST	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	372+91	55 RT	PRE-STAGE
373+22	51 RT	20	14x23	PIPE CULVERTS, CLASS A, TYPE 1 18" EQUIVALENT	2.50%	EAST	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	373+03	55 RT	PRE-STAGE
374+81	47 RT	26	14x23	PIPE CULVERTS, CLASS A, TYPE 1 18" EQUIVALENT	0.30%	EAST	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	375+03	60 RT	PRE-STAGE
374+81	51 RT	20	14x23	PIPE CULVERTS, CLASS A, TYPE 1 18" EQUIVALENT	0.30%	EAST	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	374+98	60 RT	PRE-STAGE
384+10	31 RT	5	24	PIPE CULVERTS, CLASS A, TYPE 2 24" (TEMPORARY)	1.00%	NORTH	ENDS SECTIONS 24"	384+10	36 RT	PRE-STAGE
395+17	42 LT	24	18	PIPE CULVERTS, CLASS A, TYPE 2 18" (TEMPORARY)	0.40%	NORTH	ENDS SECTIONS 18"	395+17	68 LT	STAGE I
395+17	38 RT	22	18	PIPE CULVERTS, CLASS A, TYPE 2 18" (TEMPORARY)	3.40%	NORTH	ENDS SECTIONS 18"	395+17	60 RT	PRE-STAGE

FILE NAME = s:\p\6300-6395\6346\023\micro\sh\0160132-sh\stg\mg00.dgn



1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = amanda.j	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 4/26/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**MAINTENANCE OF TRAFFIC
TEMPORARY DRAINAGE SCHEDULE**

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	11 WRS-3	KENDALL	527	91
CONTRACT NO. 60132				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				