

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN		TRAFFIC SIGNALS 0021					LIGHTING 0021		RETAINING WALL 0040		
				ROADWAY 0003		BRIDGE 0013	IL 31 AT EB US 30 RAMP			IL 31 AT WB US 30 RAMP	US 30 AT RAMP	IL 31 INTERCONNECT	KANE COUNTY	KENDALL COUNTY	KANE COUNTY
				KANE COUNTY	KENDALL COUNTY	KANE COUNTY	KANE COUNTY	VILLAGE OF MONTGOMERY	KANE COUNTY	KANE COUNTY	KANE COUNTY	KANE COUNTY	KANE COUNTY	KANE COUNTY	KANE COUNTY
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VILLAGE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1822	852	970										
48203047	HOT-MIX ASPHALT SHOULDERS, 12 1/2"	SO YD	4,772	4,772											
48203048	HOT-MIX ASPHALT SHOULDERS, 12 3/4"	SO YD	6,438	6,081	357										
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SO YD	670	417	253										
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1											
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1												
50102400	CONCRETE REMOVAL	CU YD	64	3											
50104400	CONCRETE HEADWALL REMOVAL	EACH	5	5											
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1												
50157300	PROTECTIVE SHIELD	SO YD	3,530												
50200100	STRUCTURE EXCAVATION	CU YD	2633										1075		
50300225	CONCRETE STRUCTURES	CU YD	1765										416		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2278.7										90		
50300260	BRIDGE DECK GROOVING	SO YD	6255												
50300285	FORM LINER TEXTURED SURFACE	SO FT	2928										2928		
50300300	PROTECTIVE COAT	SO YD	15,005	5890	981								286		
50500105	FURNISHING & ERECTING STRUCTURAL STEEL	L SUM	1												
50500505	STUD SHEAR CONNECTORS	EACH	24,185												
50800105	REINFORCEMENT BARS	POUND	14,870	410									14,460		

5/23/2012 3:59:20 PM

USER NAME • 1654	DESIGNED - JWB	REVISED -
PLOT SCALE • 100.0000' / IN.	DRAWN - JWB	REVISED -
PLOT DATE • 5/23/2012	CHECKED - RS	REVISED -
	DATE - 05/23/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30 AT IL ROUTE 31
SUMMARY OF QUANTITIES

SHEET NO. 500-4 OF 19

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	7
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				

Rev.