

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN		BRIDGE 0013	TRAFFIC SIGNALS 0021						LIGHTING 0021		RETAINING WALL 0040	
				ROADWAY 0003			IL 31 AT EB US 30 RAMPS		IL 31 AT WB US 30 RAMPS	US 30 AT RAMPS	IL 31 INTERCONNECT		KANE COUNTY	KENDALL COUNTY		KANE COUNTY
				KANE COUNTY	KENDALL COUNTY		KANE COUNTY	KANE COUNTY	VILLAGE OF MONTGOMERY	KANE COUNTY	KANE COUNTY	KANE COUNTY				
				80% FED 20% STATE	80% FED 20% STATE		80% FED 20% STATE	80% FED 20% STATE	100% VILLAGE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE		80% FED 20% STATE
54247210	GRATING FOR CONCRETE FLARED END SECTION 60"	EACH	6	6												
54247230	GRATING FOR CONCRETE FLARED END SECTION 72"	EACH	20	20												
54248510	CONCRETE COLLAR	CU YD	3.4	3.0	0.4											
54214509	PRECAST REINFORCED CONCRETE FLARED END	EACH	2	2												
550A0050	STORM SEWERS, CLASS A, TYPE 1 12" SECTIONS EQUIVALENT ROUND SIZE 24"	FOOT	456	456												
54240130	GRATING FOR CONCRETE FLARED END	EACH	2	2												
550A0070	STORM SEWERS, CLASS A, TYPE 1 15" SECTIONS, EQUIVALENT ROUND SIZE 24"	FOOT	156	156												
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	189	189												
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT	FOOT	32	32												
550A0120	STORM SEWERS, CLASS A, TYPE 1 24" ROUND SIZE 24"	FOOT	118	118												
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,801	1,765	36											
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	552	552												
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	119	119												
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	68	68												
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	106	106												
550A0660	STORM SEWERS, CLASS A, TYPE 3 15"	FOOT	194	194												
55100500	STORM SEWER REMOVAL 12"	FOOT	528	528												
55100700	STORM SEWER REMOVAL 15"	FOOT	699	699												
55100900	STORM SEWER REMOVAL 18"	FOOT	20	20												
55101200	STORM SEWER REMOVAL 24"	FOOT	245	245												
55101400	STORM SEWER REMOVAL 30"	FOOT	6		6											
55202000	STORM SEWERS JACKED IN PLACE, 72"	FOOT	2,488	2,488												
55101600	STORM SEWER REMOVAL 36"	FOOT	16	16												
58700300	CONCRETE SEALER	SO FT	11,690			11,690										

FILES 5/23/2012 3:59:23 PM

USER NAME * 1654	DESIGNED - JWB	REVISED -
PLOT SCALE * 100.0000' / IN.	DRAWN - JWB	REVISED -
PLOT DATE * 5/23/2012	CHECKED - RS	REVISED -
	DATE - 05/23/2012	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**U.S. ROUTE 30 AT IL ROUTE 31  
SUMMARY OF QUANTITIES**

SHEET NO. 500-7 OF 19

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	10
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				

*Rev.*