

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN		TRAFFIC SIGNALS 0021					LIGHTING 0021		RETAINING WALL 0040			
				ROADWAY 0003		BRIDGE 0013		IL 31 AT EB US 30 RAMPS		IL 31 AT WB US 30 RAMPS	US 30 AT RAMPS	IL 31 INTERCONNECT		KANE COUNTY	KENDALL COUNTY	KANE COUNTY
				KANE COUNTY	KENDALL COUNTY	KANE COUNTY	KANE COUNTY	VILLAGE OF MONTGOMERY	KANE COUNTY	KANE COUNTY	KANE COUNTY					
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VILLAGE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE			
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	3				1			1	1					
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	2145				1084			22		1,039				
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	58				58									
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	1,191				55					1,136				
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	504				504									
81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	450									450				
81100705	CONDUIT ATTACHED TO STRUCTURE, 2 1/2" DIA., PVC COATED GALVANIZED STEEL	FOOT	80									80				
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	1,760									1,760				
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	10									10				
81300800	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 12" X 6"	EACH	4									4				
81304600	JUNCTION BOX EMBEDDED IN STRUCTURE 18" X 12" X 6"	EACH	4									4				
81400100	HANDHOLE	EACH	1				1									
81400200	HEAVY-DUTY HANDHOLE	EACH	7				7									
81400300	DOUBLE HANDHOLE	EACH	2				2									
81603080	UNIT DUCT, 600V, 3*1C NO. 2, 1/C NO. 4 GROUND, (XLP*TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	2,880									2,880				
81603090	UNIT DUCT, 600V, 3*1C NO. 4, 1/C NO. 6 GROUND, (XLP*TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	6,362									5,962	400			
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP*TYPE USE) 1/C NO. 10	FOOT	1,630									1,630				

*

* Specialty Items

FILES 5/23/2012 3:59:28 PM

USER NAME * 1054	DESIGNED - JWB	REVISED -
PLOT SCALE * 100.0000 "/ IN.	DRAWN - JWB	REVISED -
PLOT DATE * 5/23/2012	CHECKED - RS	REVISED -
	DATE - 05/23/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30 AT IL ROUTE 31
SUMMARY OF QUANTITIES

SHEET NO. 500-12 OF 19

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	15
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				

Rev.