

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN											RETAINING WALL 0040		
				ROADWAY 0003		BRIDGE 0013	TRAFFIC SIGNALS 0021						LIGHTING 0021				
				KANE COUNTY	KENDALL COUNTY	KANE COUNTY	IL 31 AT EB US 30 RAMP		IL 31 AT WB US 30 RAMP	US 30 AT RAMP	IL 31 INTERCONNECT	KANE COUNTY	KENDALL COUNTY				
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	VILLAGE OF MONTGOMERY 100% VILLAGE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE			
B1702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	760													760	
B1702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	1,154													1,154	
B1702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3*1/C NO. 2	FOOT	1,154													1,154	
B1702410	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3*1/C NO. 4	FOOT	760													760	
B1702460	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3*1/C NO. 3/0	FOOT	180													180	
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	21												18	3	
82105600	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 400 WATT	EACH	60												60		
82107100	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8												8		
82500380	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 200AMP	EACH	1												1		
83050730	LIGHT POLE, ALUMINUM, 47.5 FT. M. H., 8 FT. DAVIT ARM	EACH	6												6		
83050775	LIGHT POLE, ALUMINUM, 47.5 FT. M. H., 10 FT. DAVIT ARM	EACH	15												12	3	
83502400	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 6	EACH	6												6		
83502500	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 0	EACH	3												3		
83502900	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 12	EACH	9												9		
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	150												120	30	
83700300	LIGHT TOWER FOUNDATION, 48" DIAMETER	FOOT	180												180		
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	10												8	2	
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	12												12		
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1												1		

*

*Specialty Items

3:59:30 PM 5/23/2012

USER NAME - 1654	DESIGNED - JWB	REVISED -
PLOT SCALE - 1/8" = 100'	DRAWN - JWB	REVISED -
PLOT DATE - 5/23/2012	CHECKED - RS	REVISED -
	DATE - 05/23/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30 AT IL ROUTE 31
SUMMARY OF QUANTITIES

SHEET NO. 500-13 OF 19

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11) VBI R-3	*	507	16
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				

REV