

FROM STATION	TO STATION	20200100						EXCAVATION AVAILABLE TO BE USED IN EMBANKMENT ADJUSTED			EMBANKMENT			20400800			EARTHWORK BALANCE: WASTE (+) OR SHORTAGE (-)			FURNISHED EXCAVATION (SHRINKAGE FACTOR = 15%)			WASTE HAUL OFF (SWELL FACTOR 15%)		
		EARTH EXCAVATION			CU YD			CU YD			CU YD			CU YD			CU YD			CU YD					
		STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage			
Ramp B																									
403+00	403+50		60		0	51	0	1900				-1900	51	0	2235	0	0	0	60	0					
403+50	404+00				0	0	0	2312				-2312	0	0	2720	0	0	0	0	0					
404+00	404+50				0	0	0	2280				-2280	0	0	2682	0	0	0	0	0					
404+50	405+00				0	0	0	2043				-2043	0	0	2404	0	0	0	0	0					
405+00	405+50				0	0	0	1580				-1580	0	0	1859	0	0	0	0	0					
405+50	406+00				0	0	0	701				-701	0	0	825	0	0	0	0	0					
406+00	406+50				0	0	0	457				-457	0	0	538	0	0	0	0	0					
406+50	407+00				0	0	0	730				-730	0	0	859	0	0	0	0	0					
407+00	407+50		0		0	0	0	719				-719	0	0	846	0	0	0	0	0					
407+50	408+00																								
408+00	408+50		0		0	0	0	1505				-1505	0	0	1771	0	0	0	0	0					
408+50	409+00				0	0	0	787				-787	0	0	926	0	0	0	0	0					
409+00	409+50				0	0	0	765				-765	0	0	900	0	0	0	0	0					
409+50	410+00				0	0	0	702				-702	0	0	826	0	0	0	0	0					
410+00	410+50				0	0	0	796				-796	0	0	936	0	0	0	0	0					
410+50	411+00				0	0	0	759				-759	0	0	893	0	0	0	0	0					
411+00	411+50				0	0	0	593				-593	0	0	698	0	0	0	0	0					
411+50	412+00				0	0	0	554				-554	0	0	652	0	0	0	0	0					
412+00	412+50				0	0	0	523				-523	0	0	615	0	0	0	0	0					
Ramp C																									
501+00	501+50	0			0	0	0	337				-337	0	0	396	0	0	0	0	0					
501+50	502+00	0			0	0	0	457				-457	0	0	538	0	0	0	0	0					
502+00	502+50	0			0	0	0	579				-579	0	0	681	0	0	0	0	0					
502+50	503+00	0			0	0	0	710				-710	0	0	835	0	0	0	0	0					
503+00	503+50	0			0	0	0	946				-946	0	0	1113	0	0	0	0	0					
503+50	504+00	0			0	0	0	778				-778	0	0	915	0	0	0	0	0					
504+00	504+50	0			0	0	0	421				-421	0	0	495	0	0	0	0	0					
504+50	505+00	0			0	0	0	772				-772	0	0	908	0	0	0	0	0					
505+00	505+50	0			0	0	0	1310				-1310	0	0	1541	0	0	0	0	0					
505+50	506+00	0			0	0	0	1450				-1450	0	0	1706	0	0	0	0	0					
506+00	506+50	4			3	0	0	903				-900	0	0	1058	0	0	0	0	0					
506+50	507+00	98			83	0	0	218				-135	0	0	158	0	0	0	0	0					

FILE# 5/15/2012 11:33:55 PM

USER NAME = 1654	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - RS	REVISED -
PLOT DATE = 5/15/2012	DATE - 05/11/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**U.S. ROUTE 30 AT IL ROUTE 31
EARTHWORK SCHEDULES**

SCALE: N.T.S. SHEET NO. 2 OF 5

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	42
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				