

FROM STATION	TO STATION	20200100						EXCAVATION AVAILABLE TO BE USED IN EMBANKMENT ADJUSTED			EMBANKMENT			20400800			EARTHWORK BALANCE: WASTE (+) OR SHORTAGE (-)			FURNISHED EXCAVATION (SHRINKAGE FACTOR = 15%)			WASTE HAUL OFF (SWELL FACTOR 15%)		
		EARTH EXCAVATION			CU YD			CU YD			CU YD			CU YD			CU YD			CU YD					
		STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage	STAGE 1	STAGE 2	Prestage			
1261+00	1261+50	266			226	0	0	105			121	0	0	0	0	0	142	0	0						
1261+50	1262+00	265			225	0	0	116			109	0	0	0	0	0	129	0	0						
1262+00	1262+50	272			231	0	0	108			123	0	0	0	0	0	145	0	0						
1262+50	1263+00	290			247	0	0	70			177	0	0	0	0	0	208	0	0						
1263+00	1263+50	339			288	0	0	14			274	0	0	0	0	0	323	0	0						
1263+50	1264+00				0	0	0	311			-311	0	0	366	0	0	0	0	0						
1264+00	1264+50	364			309	0	0	4			305	0	0	0	0	0	359	0	0						
1264+50	1265+00	216			184	0	0	95			89	0	0	0	0	0	104	0	0						
1265+00	1265+50	207			176	0	0	168			8	0	0	0	0	0	9	0	0						
1265+50	1266+00	323			275	0	0	217			58	0	0	0	0	0	68	0	0						
1266+00	1266+50	290			247	0	0	623			-377	0	0	443	0	0	0	0	0						
1266+50	1267+00	258			219	0	0	788			-569	0	0	669	0	0	0	0	0						
1267+00	1267+50	243			207	0	0	488			-281	0	0	331	0	0	0	0	0						
1267+50	1268+00	241			205	0	0	416			-211	0	0	248	0	0	0	0	0						
1268+00	1268+50	Bridge Location																							
1268+50	1269+00	Bridge Location																							
1269+00	1269+50	Bridge Location																							
1269+50	1270+00	Bridge Location																							
1270+00	1270+50	Bridge Location																							
1270+50	1271+00	Bridge Location																							
1271+00	1271+50	Bridge Location																							
1271+50	1272+00	Bridge Location																							
1272+00	1272+50	Bridge Location																							
1272+50	1273+00	Bridge Location																							
1273+00	1273+50	Bridge Location																							

FILE# 5/15/2012 11:34:01PM

USER NAME = 1654	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - RS	REVISED -
PLOT DATE = 5/15/2012	DATE - 05/11/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**U.S. ROUTE 30 AT IL ROUTE 31
EARTHWORK SCHEDULES**

SCALE: N.T.S. SHEET NO. 5 OF 5

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	46
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				