

LOCATION		60600605		60602800		60605000		63000001		63100085		63100167		64300240		64300240	
		CONCRETE CURB, TYPE B		CONCRETE GUTTER, TYPE B		COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24		STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS		TRAFFIC BARRIER TERMINAL, TYPE 6		TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT		IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2		IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	
		(FT)		(FT)		(FT)		(FT)		(EACH)		(EACH)		(EACH)		(EACH)	
STATION	STATION	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT
US 30																	
KANE																	
1234+00	1249+00	0	0	0	0	0	0	450.5	0.0	0	0	1	0	0	0	0	0
1249+00	1261+00	0	0	460	0	0	0	262.0	0.0	2	0	1	0	0	0	0	0
1261+00	1275+00	0	0	0	0	0	0	0.0	0.0	0	1	0	1	0	0	0	1
1275+00	1277+13 / 1278+21	0	0	0	0	0	0	0.0	0.0	0	0	0	0	0	0	0	1
KENDALL																	
1277+13 / 1278+21	1281+00	0	0	0	0	0	0	0.0	0.0	0	0	0	0	0	0	0	0
IL 31																	
KENDALL																	
79+00	92+00	0	0	0	0	0	0	0.0	0.0	0	0	0	0	0	0	0	0
92+00	100+00	0	0	0	0	0	0	0.0	0.0	0	0	0	0	0	0	0	0
100+00	106+11 / 107+36	0	0	0	0	0	0	0.0	0.0	0	0	0	0	0	0	0	0
KANE																	
106+11 / 107+36	111+00	0	0	0	0	150	0	0.0	0.0	0	0	0	0	0	0	0	0
111+00	124+00	0	0	0	0	302	149	12.5	0.0	0	0	1	0	0	0	0	0
124+00	138+00	131	0	0	0	1293	529	0.0	0.0	0	0	0	0	0	0	0	0
138+00	140+70	0	0	0	0	0	0	0.0	0.0	0	0	0	0	0	0	0	0
RAMP A																	
300+00	315+00	0	0	0	0	0	0	0.0	0.0	0	0	0	0	1	0	0	0
315+00	317+80	0	0	0	0	0	0	0.0	0.0	0	0	0	0	0	0	0	0
RAMP B																	
400+00	413+34	0	0	0	0	0	0	0.0	0.0	0	0	0	0	0	0	0	0
RAMP C																	
500+00	509+54	0	0	0	0	0	0	275.0	0.0	0	0	1	0	0	0	0	0
RAMP D																	
600+00	611+65	0	0	0	0	0	0	0.0	162.5	0	0	0	1	0	0	0	0
KANE		131		460		2423		1163		3		6		1		2	
KENDALL		0		0		0		0		0		0		0		0	
TOTALS		131		460		2423		1163		3		6		1		2	

P:\Jobs\2010\20103003\cd\site\vgd\00\0160133-sht+Schedule-Roadway.dgn
 6/15/2012 3:44:57 PM

USER NAME = 1654	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - RS	REVISED -
PLOT DATE = 6/15/2012	DATE - 06/15/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30 AT IL ROUTE 31
ROADWAY SCHEDULE

SHEET NO. 3 OF 3

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	48A
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				