

P:\Jobs\2010\20103003\cd\site\cd\site\00\0160133-sht+-Schedule-SewerRemoval.dgn  
 6/15/2012 3:45:07 PM

LOCATION						55100500	55100700	55100900	55101200	55101400	55101600		59300100	60300305	60500040	60500050	60500060	
						STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	STORM SEWER REMOVAL 24"	STORM SEWER REMOVAL 30"	STORM SEWER REMOVAL 36"	PLUG AND ABANDON SEWER	CONCRETE BOX CULVERT REMOVAL, 10' X 6'	CONTROLLED LOW-STRENGTH FILL MATERIAL	FRAMES AND LIDS TO BE ADJUSTED	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS
						( FT )	( FT )	( FT )	( FT )	( FT )	( FT )	( FT )	( FT )	( CU YD )	( EACH )	( EACH )	( EACH )	( EACH )
STATION	OFFSET	LT/RT	STATION	OFFSET	LT/RT													
106+15	94.1	LT								8								
106+68	97.6	LT								8								
109+49	89	LT																
109+49	89	LT	109+76	46	RT							123						
109+76	46	RT																
109+49	121.2	LT											1					
109+90	26	LT														1		
109+90	26	LT	109+69	1.2	RT					35								
110+05	107.4	LT				2												
110+24	87.8	RT	110+05	107.4	LT	28												
110+43	68.3	KT	110+24	87.8	RT					10								
110+52	163.7	LT															1	
110+52	163.7	LT	110+30	163.5	LT		24											
110+30	163.5	LT					2											
111+00	164.6	LT															1	
111+00	164.6	LT	111+22	165.7	LT	24												
111+22	165.7	LT				2												
111+25	24.5	LT															1	
111+25	24.5	LT	111+25	0	RT		25											
111+25	0	RT	111+23	54.9	RT					15								
111+23	54.9	RT					6											
112+71	91.8	LT				2												
112+71	91.8	LT	112+72	72.3	LT			20										
112+72	72.3	LT	112+74	24.8	LT					48								
112+74	24.8	LT	112+73	0	RT			25										
112+73	0	RT	112+76	31.4	RT					32								
UNKNOWN	UNKNOWN	LT	114+03	1.5	LT	13												
114+03	1.5	LT															1	
114+03	1.5	LT	113+72	0.9	LT		32											
115+77	112.8	LT																
117+50	21.5	LT															1	
117+50	21.5	LT	118+89	7.2	LT		138											
118+89	7.2	LT														1		
118+89	7.2	LT	119+05	15.3	LT		18											
117+66	111.9	LT															1	
117+66	111.9	LT	117+53	134.2	LT	25												
118+39	122.1	LT															1	
118+39	122.1	LT	118+39	136.6	LT		15											
118+60	141.5	LT																
118+60	141.5	LT	117+42	139	LT					107								
117+42	139	LT																
122+09	1.7	RT															1	
122+09	1.7	RT	122+09	61.6	LT	63												
123+39	52.5	LT				2												
126+88	43.5	RT						2										
126+88	43.5	RT	126+87	39.3	LT			83										
126+87	39.3	LT						2										
RAMP A																		
UNKNOWN	UNKNOWN	LT	311+10	65.9	LT	30												
311+10	65.9	LT				2												

USER NAME = 1654	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - RS	REVISED -
PLOT DATE = 6/15/2012	DATE - 06/15/2012	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**U.S. ROUTE 30 AT IL ROUTE 31**  
**SEWER REMOVAL SCHEDULES**

SHEET NO. 2 OF 6

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	49C
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				