

LOCATION						55100500	55100700	55100900	55101200	55101400	55101600		59300100	60300305	60500040	60500050	60500060		
						STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	STORM SEWER REMOVAL 24"	STORM SEWER REMOVAL 30"	STORM SEWER REMOVAL 36"	PLUG AND ABANDON SEWER	CONCRETE BOX CULVERT REMOVAL, 10' X 6'	CONTROLLED LOW-STRENGTH FILL MATERIAL	FRAMES AND LIDS TO BE ADJUSTED	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	
						(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(CU YD)	(EACH)	(EACH)	(EACH)	(EACH)	
STATION	OFFSET	LT/RT	STATION	OFFSET	LT/RT														
314+29	1.7	LT															1		
314+29	1.7	LT	314+30	9	RT	11													
314+30	9	RT				2													
RAMP B																			
406+05	70.7	LT															1		
406+05	70.7	LT	405+89	70.7	LT		20												
405+89	70.7	LT															1		
405+89	70.7	LT	405+58	69.5	LT		38												
405+58	69.5	LT					2												
405+33	222.7	LT															1		
405+33	222.7	LT	405+23	176.5	LT		49												
405+23	176.5	LT					2												
RAMP C																			
504+86	43.8	LT															1		
504+86	43.8	LT	505+04	15.8	LT	35													
505+04	15.8	LT				2													
RAMP D																			
603+28	29.9	RT															1		
603+28	29.9	RT	603+28	57.1	RT		27												
603+28	57.1	RT					2												
605+14	54.6	LT					2												
605+14	54.6	LT	605+49	40.3	RT		101												
605+49	40.3	RT					2												
						KANE	528	699	20	245	0	16	140	107	123	3	0	1	27
						KENDALL	0	0	0	0	6	0	0	0	0	0	0	0	4
						TOTALS	528	699	20	245	6	16	140	107	123	3	0	1	31

P:\Jobs\2010\20103003\cd\sheet\sheet.dgn\00\0160133-sht-Schedule-SewerRemoval.dgn
 6/15/2012 3:45:08 PM

USER NAME = 1654	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - RS	REVISED -
PLOT DATE = 6/15/2012	DATE - 06/15/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30 AT IL ROUTE 31
SEWER REMOVAL SCHEDULES

SHEET NO. 3 OF 6

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	49D
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				